AMENDMENT OF SOLICITATION / MODIFICATION OF CONTRACT	1. Contract Number	Page of Pages	
		1	1

2. Amendment/Modification Number	3. Effective Date	4. Requisition/Purchase Request No.	5. Solicitation Caption
DCAM-2009-B-0021-003	May 18, 2009		Upgrade of the Parking Garage and Plaza Lighting at UDC

6. Issued by: Code LRT	7. Administered by (If other than line 6)
Office of Contracting and Procurement Construction, Design and Building Renovation 441 4th Street, NW, Suite 700S Washington, DC 20001	Office of Contracting and Procurement 2000 14th Street, N.W., 3rd Floor Washington, DC 20009

8. Name and Address of Contractor (No. street, city, county, state and zip code)		9A. Amendment of Solicitation No. DCAM-2009-B-0021
		9B. Dated (See Item 11) April 13, 2009
		10A. Modification of Contract/Order No.
Code / DUNS: / TIN / FEIN:		10B. Dated (See Item 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended. Offeror's must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning 2 copies of the amendment: (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) BY separate letter or fax which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such may be made by letter or fax, provided each letter or telegram makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. Accounting and Appropriation Data (If Required) *To be cited on individual orders issued on behalf of participating agencies*

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14

X	A. This change order is issued pursuant to (Specify Authority): 27 DCMR, Chapter 36, Section 3603 The changes set forth in Item 14 are made in the contract/order no. in item 10A.
	B. The above numbered contract/order is modified to reflect the administrative changes (such as changes in paying office, appropriation data etc.) set forth in item 14, pursuant to the authority of
	C. This supplemental agreement is entered into pursuant to authority of:
	D. Other (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not ☒ is: required to sign this document and return 2 copies with bids.

14. Description of Amendment/Modification (Organized by UCF Section headings, including solicitation/contract subject matter where feasible

A. Delete Section B.3 in its entirety and substitute the following:

B.3 "The District contemplates award of a firm fixed-price contract. The estimated price range for this requirement is between $1,000,000.00 - $5,000,000.00.

B. Delete Section B.4 in its entirety and substitute the following:

B.4 "The Contractor must bid lump sum firm fixed price for the following Contract Line Item Number (CLIN) as described below. (Attachment A should be included in the lump sum price)

C. Delete Section B.6 and Section B.7 in its entirety.

D. The opening date, time and place remain the same. (May 22, 2009 at 2:00 p.m.)

Except as provided herein, all terms and conditions of the document is referenced in Item 9A or 10A remain unchanged and in full force and effect.

15A. Name and Title of Signer (Type or print)		16A. Name of Contracting Officer Diane Wooden	
15B. Name of Contractor (Signature of person authorized to sign)	15C. Date Signed	16B. District of Columbia Diane Wooden (Signature of Contracting Officer)	16C. Date Signed 5/18/09

Attachment A

1. ELIMINATE WORK RELATED TO FIXTURES IDENTIFIED AS TYPES "CC", "C1", "C2, "C4", "B0" AND "M1." ALL EXISTING LIGHTING POLES AND BOLLARDS SHALL REMAIN.

2. ELIMINATE ALL WIRING AND CONDUIT ASSOCIATED WITH THE LIGHTING FIXTURES MENTIONED IN THE PREVIOUS ITEM.

3. ADD THE FOLLOWING EXIT LIGHTS AND CONNECT THEM TO THE NEAREST EMERGENCY CIRCUIT.

   DRAWING GR-E.2

   A. ADD ONE EXIT LIGHT TYPE "H1" IN FRONT OF EXIT STAIR NEAR COLUMN LINE "22" AND "23" AND COLUMN LINE "A" AND "B."
   B. ADD ONE EXIT LIGHT TYPE "H" IN FRONT OF THE ENTRANCE DOOR TO BUILDING 41 BETWEEN COLUMN LINE "H.9" AND "I.5" AND COLUMN LINES "20" AND "21."
   C. ADD ONE EXIT LIGHT TYPE "H" IN FRONT OF EXIT STAIRWELL DOOR BETWEEN COLUMN LINE "H.9" AND "I.5" AND COLUMN LINE "9" AND "10."
   D. ADD ONE EXIT LIGHT TYPE "H" IN FRONT OF EXIT STAIRWELL DOOR BETWEEN COLUMN LINE "C" & "D" AND COLUMN LINES "7" & "8."
   E. ADD ONE EXIT LIGHT TYPE IN FRONT OF THE MAIN VEHICLE EXT BETWEEN LINES "B" AND "C" AND COLUMN LINE "17" AND "18."

4. THE EMERGENCY POWER AND LIGHTING SHALL BE PROVIDED AS PART OF THE BASE BID.

5. DRAWING EG-1 BASIC MATERIALS AND METHODS. ADD THE FOLLOWING NOTE:
   17. ALL EXTERIOR ELECTRICAL WORK, WORK IN WET LOCATIONS AND WORK IN THE GARAGE SHALL BE WATERPROOFED.

6. DRAWING E-10
   A. ELIMINATE NOTE 58.
   B. ALL REFERENCES TO NOTE 58 SHALL CHANGE TO NOTE 12.
   C. REVISE NOTE 12 TO READ:
   NOTE 12. CLEAN AND REPAIR EXISTING PANELS AS NEEDED. PROVIDE NEW DOORS AND COVERS AND OTHER ACCESSORIES AS NEEDED FOR A COMPLETE INSTALLATION. PROVIDE NEW LABELS AND PANEL DIRECTORIES. RESTORE PANELS TO LIKE NEW CONDITION.

7. DRAWING E-11
   A. REVISE THE FOLLOWING PANEL SCHEDULES AS FOLLOWS:

   (1) PANEL E44DP SHALL BE A NEW PANEL WITH 30K AIC IN LIEU OF THE "EXISTING" INDICATED ON THIS DRAWING.
   (2) PANELS "G44-DP", "41 DPA" AND "44-DPA" SHALL BE A NEW PANEL IN LIEU OF EXISTING INDICATED ON THIS DRAWING.

   B. PANEL "EMGB" SHALL BE LOCATED IN BUILDING 44 ELECTRICAL ROOM NEXT TO PARKING LEVEL "B" IN LIEU OF THE PARKING LEVEL "C" INDICATED.
   C. PANEL EMG SHALL BE LOCATED IN BUILDING 41 ELECTRICAL ROOM LEVEL B.

8. IF NEW CIRCUIT BREAKERS ARE SHOWN TO BE INSTALLED IN EXISTING PANELBOARDS AND IF THE EXISTING PANELBOARDS CANNOT ACCOMMODATE THE INSTALLATION OF THE NEW CIRCUIT BREAKERS, THEN THE CONTRACTOR SHALL PROVIDE NEW FEEDERS AND TAP THE EXISTING PANEL AS PERMITTED BY NEC AND PROVIDE NEW PANELS AND CIRCUIT BREAKERS

IN NEMA ENCLOSURE AS CLOSE AS POSSIBLE TO THE EXISTING PANELS. INSTALL REQUIRED CIRCUIT BREAKERS IN NEW PANELS.

9. RELOCATE EXISTING ELECTRICAL EQUIPMENT AS NEEDED TO ACCOMMODATE THE INSTALLATION OF THE NEW WORK.

10. COORDINATE THE PLACEMENT OF ALL ELECTRICAL WORK IN THE FIELD. RELOCATE WORK AS NEEDED. COORDINATE RELOCATION WITH THE PROJECT COORDINATOR AND RELOCATE AS DIRECTED.

11. IDENTIFY ALL NEW OR EXISTING PANELS IN WHICH WORK IS BEING PERFORMED WITH A PHENOLIC PLATE AND A MINIMUM 1" HIGH LETTERING. USE BLACK PLATE FOR NORMAL POWER AND RED FOR EMERGENCY POWER.

12. WHEN NEW LIGHTING FIXTURES ARE INSTALLED ON EXISTING PLASTER CEILINGS THE LIGHTING FIXTURES SHALL BE RIGIDLY SUPPORTED THROUGH CHANNEL LINES FROM THE STRUCTURE ABOVE. THE NEW CONDUIT SHALL BE INSTALLED RECESSED WITHIN THE PLASTER CEILING AND SHALL BE SUPPORTED FROM THE STRUCTURE ABOVE. THE CONTRACTOR SHALL CUT, PATCH, REPAIR AND REFINISH THE EXISTING PLASTER CEILING AFTER THE INSTALLATION OF THE NEW CONDUITS SUPPORTS OF THE NEW LIGHTING FIXTURES.

    THE CONTRACTOR SHALL VERIFY THE AREAS WHERE PLASTER CEILINGS ARE INSTALLED.

    IN THE AREAS WITH PLASTER CEILINGS INCLUDED ARE:
    A. THE AREA BETWEEN COLUMN LINES "11" AND "19" AND BETWEEN COLUMN LINES "K" AND "N."
    B. THE BUILDING CANOPIES, ETC.

    FIELD VERIFY ALL SUCH AREAS AND PROVIDE INSTALLATION AS DESCRIBED ABOVE.

13. REPAIR OR REMOVE AND REPLACE WITH NEW ALL EXISTING LIGHTING CONTROL DEVICES THAT ARE NOT FUNCTIONING PROPERLY. THIS CATEGORY INCLUDES: MOTION DETECTORS, PHOTOCELLS, CONTACTORS, TIME SWITCHES AND OTHER RELATED EQUIPMENT AS NEEDED FOR A PROPER OPERATION OF THE NEW AND EXISTING LIGHTING SYSTEM SERVING THE AREA OF WORK.

14. BUILDING 41 ADD 6 - 1000W, MH, 277V FLOOD LIGHTS SIMILAR TO EXISTING FIXTURE TYPE "A1." MOUNT FIXTURES NEAR THE TOP OF THE BUILDING TO ILLUMINATE THE PLAZA DECK FROM ABOVE. LOCATE LIGHTS AS NEEDED TO PROVIDE EVEN PLAZA ILLUMINATION AROUND BUILDING 41.

    NEW LIGHTING FIXTURES SHALL BE EQUIPPED WITH BUILT-IN PHOTOCELLS.
    MOUNT FIXTURES RIGIDLY FROM THE EXISTING BUILDING WALL AS NEEDED. PROVIDE BASES, BRACKETS AND OTHER ACCESSORIES AS NEEDED FOR RIGID INSTALLATIONS.

    GROUP 2 OF THESE 6 LIGHTS TO ONE 20A/277V CIRCUIT. CONNECT THESE CIRCUITS TO 3-1P-20A NEW CIRCUIT BREAKERS IN PANEL 44-HG-5A, WITH 2#6+1#8G-1"C PER CIRCUIT. RUN EACH CIRCUIT TO THE PANEL THROUGH A 7 DAY TIME SWITCH.

    RUN CONDUITS CONCEALED WITHIN BUILDING 41 TO THE GARAGE. RUN CONDUIT SURFACE MOUNTED WITHIN THE GARAGE TO PANEL 44-HG-5A.

15. BUILDING 47

    ADD 3- 400W, MH, 277V FLOOD LIGHTS, SIMILAR TO THE EXISTING FIXTURE TYPE "A1."

MOUNT FIXTURES NEAR THE TOP OF THE BUILDING TO ILLUMINATE THE DECK IN FRONT OF THE MAIN ENTRANCE.

LOCATE LIGHTS AS NEEDED TO PROVIDE EVEN ILLUMINATION OF THE AREA IN FRONT OF THE BUILDING 47.

NEW LIGHTING FIXTURES SHALL BE EQUIPPED WITH BUILT-IN PHOTOCELLS.

MOUNT FIXTURES RIGIDLY FROM THE EXISTING BUILDING WALL AS NEEDED. PROVIDE BASES, BRACKETS AND OTHER ACCESSORIES AS NEEDED FOR A RIGID INSTALLATION.

CONNECT THESE 3 NEW LIGHTS TO A 1P-20A, 277V NEW CIRCUIT BREAKER IN PANEL 44-HG-5A WITH 2#6+1#8G-1"C.

RUN CIRCUIT TO THE PANEL THROUGH A 7 DAY TIME SWITCH.

RUN CONDUIT CONCEALED WITHIN BUILDING 47 AND UNDERGROUND 36" BELOW GRADE AND SURFACE MOUNTED WITHIN THE GARAGE TO THE PANEL 44-HG-5A.

16. CUT, PATCH AND REFINISH ALL DISTURBED SURFACES TO MATCH SURROUNDING CONDITIONS.

17. GENERAL

    1. UNLESS OTHERWISE SHOWN, ALL REFURBISHED OR NEW FIXTURES IN THE CANOPIES SHALL BE CONNECTED TO THE EXISTING LIGHTING CIRCUIT SERVING THE REMOVED OR EXISTING LIGHTING FIXTURE. CONTRACTOR SHALL VERIFY CONTINUITY OF CIRCUIT AND VOLTAGE AS NEEDED.

    2. PROVIDED TEMPORARY LIGHTING DURING CONSTRUCTION AS NECESSARY TO ILLUMINATE ALL OCCUPIED AREAS, PATHWAYS, ETC. OF THE SPACE WHOSE LIGHTING HAS BEEN AFFECTED BY THE INSTALLATION OF THE NEW WORK. PROVIDE TEMPORARY POWER AS NEEDED.

18. DRAWING DE-1
    1. NOTES

    NOTE 1 SHOULD READ:
    1. SEE LIGHTING FIXTURE SCHEDULES ON DRAWING EG-2 IN LIEU OF EG-1 INDICATED.
    2. DRAWING DE-1 PERTAINS PRIMARILY TO THE DEMOLITION WORK OF THIS PROJECT. FOR NEW WORK SYMBOLS, ABBREVIATIONS AND NOTES SEE DRAWING EG-1 AND OTHER NEW WORK DRAWINGS.

19. DRAWING EG-2

    FIXTURES TYPE "AB" AND "AC":

    PROVIDE A 100W QUARTZ STANDBY ATTACHMENT VS THE 55W HO CIRCLE LINE FLUORESCENT SPECIFIED.