

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. Contract Number	Page of Pages 1 16	
2. Amendment/Modification Number 5	3. Effective Date See box 16C	4. Requisition/Purchase Request No. N/A		5. Solicitation Caption Recon. of Nebraska Ave., N.W.	
6. Issued By: DDOT District Department of Transportation Office of Contracting and Procurement 2000 14th Street, NW, 6th Floor Washington, DC 20009		Code	7. Administered By (If other than line 6) Department of Public Works Office of Contracting and Procurement 2000 14th Street, NW, 3rd Floor Washington, DC 20009		
8. Name and Address of Contractor (No. Street, city, country, state and ZIP Code)			(X)	9A. Amendment of Solicitation No. DCKA-2007-B-0137	
				9B. Dated (See Item 11)	
				10A. Modification of Contract/Order No.	
				10B. Dated (See Item 13)	
Code	Facility		11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS		
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input type="checkbox"/> is extended. <input checked="" type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or fax which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or fax, provided each letter or telegram makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.					
12. Accounting and Appropriation Data (If Required)					
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14					
A. This change order is issued pursuant to: (Specify Authority) The changes set forth in Item 14 are made in the contract/order no. in item 10A.					
B. The above numbered contract/order is modified to reflect the administrative changes (such as changes in paying office, appropriation date, etc.) set forth in item 14, pursuant to the authority of 27 DCMR, Chapter 36, Section 3601.2.					
C. This supplemental agreement is entered into pursuant to authority of:					
D. Other (Specify type of modification and authority)					
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input checked="" type="checkbox"/> is required to sign this document and return <u>1</u>					
14. Description of amendment/modification (Organized by UCF Section headings, including solicitation/contract subject matter where feasible.) Amendment No. 5 is being issued to extend the bid opening from April 2, 2008 to April 9, 2008. Delete pay items pages 1 through 14. Replace with revised pay items pages 1R through 14R and add page 15. Hereto are the revised pay items pages 1R through 14 and page 15.					
Except as provided herein, all terms and conditions of the document referenced in Item (9A or 10A) remain unchanged and in full force and effect					
15A. Name and Title of Signer (Type or print)			16A. Name of Contracting Officer Jerry M. Carter		
15B. Name of Contractor		15C. Date Signed	16B. District of Columbia		16C. Date Signed
(Signature of person authorized to sign)			(Signature of Contracting Officer)		

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PARTICIPATING ROADWAY WORK						
0010	000003 Employee Training	1500.000				
		HR	.		.	
0020	000111 Materials Special Item - SY - INSTALL GEOTEXTILE FABRIC ITEM 213 003	4700.000				
		SY	.		.	
0030	108002 Progress Photographs		LUMP	LUMP		
					.	
0040	108004 As-Built Drawings		LUMP	LUMP		
					.	
0050	202002 Common Excavation	12250.000				
		CY	.		.	
0060	204002 Embankment Fill	500.000				
		CY	.		.	
0070	204004 Borrow Embankment Fill	2450.000				
		CY	.		.	
0080	205002 Structure Excavation	350.000				
		CY	.		.	
0090	207002 Trench Excavation and Backfill	450.000				
		CY	.		.	
0100	207008 Borrow Trench Backfill	150.000				
		CY	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	208002 Pervious Fill	100.000 CY	.		.	
0120	209002 Aggregate Base Course	3550.000 CY	.		.	
0130	209991 Aggregate Base Course Special Item -CY- # 57 COARSE AGGREGATE ITEM 209 009	15.000 CY	.		.	
0140	212002 Test Pit	20.000 EACH	.		.	
0150	302002 Valve Casing	1.000 EACH	.		.	
0160	305002 Ductile Iron Pipe, 4 - 8 Inch	20.000 LF	.		.	
0170	305018 Extra Fittingd - Contractor Furnished	10.000 LBS	.		.	
0180	306002 Gate Butterfly Valve, 3 - 12 Inch	1.000 EACH	.		.	
0190	307010 Convert Fire Hydrant	4.000 EACH	.		.	
0200	310008 Basin Connect PCC Pipe, Class III, 15 Inch	100.000 LF	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	310991 Catch Basins Connecting Pipe Special Item - LF - ITEM 311 035 CLEAN PCC PIPE	200.000 LF	.		.	
0220	310992 Catch Basins Special Item -EACH - STANDARD DUAL THROAT WATER QUALITY BASIN ITEM 310 005	3.000 EACH	.		.	
0230	311002 Adjust Sewer-Water-Utility Manhole Frame	50.000 EACH	.		.	
0240	311004 Reset Sewer-Water-Utility Manhole Frame	10.000 EACH	.		.	
0250	311991 Adjust, Rebuild&Replace Manhole&Catchbasin- Special Item -EA- ITEM 311 033 CLEAN SEWER STRUCTURE	10.000 EACH	.		.	
0260	311991 Adjust, Rebuild&Replace Manhole&Catchbasin- Special Item -EA- REPLACE EXISTING BASIN W/DUAL THROAT WATER QUALITY BASIN ITEM 311029	12.000 EACH	.		.	
0270	311991 Adjust, Rebuild&Replace Manhole&Catchbasin- Special Item -EA- REPLACE EXISTING BASIN WITH SINGLE THROA WATER QUALITY BASIN ITEM 311027	2.000 EACH	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0280	313002 Abandon Basin Connecting Pipe	3.000 EACH	.		.	
0290	313006 Abandon Basin	3.000 EACH	.		.	
0300	402002 Superpave Base Course, 19 mm	5300.000 TON	.		.	
0310	402010 Superpave Surface Course, 9.5 mm	1850.000 TON	.		.	
0320	403002 Tack Coat	11900.000 SY	.		.	
0330	407002 Temporary AC, Superpave Surface Course, 12.5 mm	100.000 TON	.		.	
0340	502004 PCC Base for Utility Cuts	20.000 CY	.		.	
0350	504006 PCC Driveway-Alley Entrance, 7 Inch	750.000 SY	.		.	
0360	602012 Special PCC Coping PCC COPING	20.000 CY	.		.	
0370	603004 Underdrain Pipe, 6 Inch	250.000 LF	.		.	
0380	603006 Underdrain Pipe, 8 Inch	225.000 LF	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0390	606002 Pavement Profiling (Milling)	500.000 SY	.		.	
0400	608004 PCC Sidewalk, 4 Inch	2400.000 SY	.		.	
0410	608016 Repair-Replace PCC Sidewalk, 4 Inch	80.000 SY	.		.	
0420	609002 PCC Curb and/or Gutter	10.000 CY	.		.	
0430	609038 PCC Gutter, 7 to 10 Inch Depth x 12-24 Inch Width	680.000 SY	.		.	
0440	609050 Repair-Replace PCC Curb and/or Gutter	10.000 CY	.		.	
0450	609068 Furnish and Set 8"x12" Granite Straight Curb	4800.000 LF	.		.	
0460	609070 Furnish and Set 8"x12" Granite Circular Curb, Radius Under 10 Ft.	220.000 LF	.		.	
0470	609072 Furnish and Set 8"x12" Granite Circular Curb, Radius 10-100 Ft.	600.000 LF	.		.	
0480	609200 PCC Wheelchair/Bicycle Ramp - New Construction	26.000 EACH	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0490	610018 Sod with 3 Inch Topsoil	2500.000 SY	.		.	
0500	611002 Remove Tree and Stump up to 6 Inch Dia.	1.000 EACH	.		.	
0510	611004 Remove Tree and Stump 6 to 12 Inch Dia.	4.000 EACH	.		.	
0520	611006 Remove Tree and Stump 12 to 18 Inch Dia.	3.000 EACH	.		.	
0530	611010 Remove Tree and Stump 24 to 30 Inch Dia.	1.000 EACH	.		.	
0540	611014 Remove Tree and Stump 36 to 42 Inch Dia.	1.000 EACH	.		.	
0550	611030 Remove Tree Stump 12 to 24 Inch Dia	1.000 EACH	.		.	
0560	611042 Prune Tree 12 Inch to 18 Inch Dia.	1.000 EACH	.		.	
0570	611044 Prune Tree 18 Inch to 24 Inch Dia.	1.000 EACH	.		.	
0580	612002 Mobilization	LUMP	LUMP		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0590	614992 PCC Traffic Barriers Special Item - LF - INSTALL PORTABLE PCC BARRIER ITEM 614 013	2200.000 LF	.		.	
0600	614992 PCC Traffic Barriers Special Item - LF - MOVE PORTABLE PCC BARRIER ITEM 614 015	2200.000 LF	.		.	
0610	615004 Three-Ply Membrane Waterproofing	100.000 SY	.		.	
0620	616004 Construction Lane Closing	LUMP		LUMP		.
0630	616006 Remove Lane Markings	100.000 SF	.		.	
0640	616008 Temporary Construction Sign Supports	50.000 EACH	.		.	
0650	616012 Construction Warning and Detour Signs	400.000 SF	.		.	
0660	616014 Reflectorized Traffic Cones	200.000 EACH	.		.	
0670	616016 Flashing Amber Warning Lights, Type "B"	20.000 EACH	.		.	
0680	616022 Construction Sign Warning Flags	20.000 EACH	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0690	616024 Type III PVC Barricade	20.000 EACH	.		.	
0700	616028 Traffic Drums	200.000 EACH	.		.	
0710	616040 Thermoplastic Pavement Marking, 4 Inch	10600.000 LF	.		.	
0720	616044 Thermoplastic Pavement Marking, 6 Inch	1230.000 LF	.		.	
0730	616050 Thermoplastic Pavement Marking, 12 Inch	1678.000 LF	.		.	
0740	616060 Painted Lane Marking, 4 Inch	1000.000 LF	.		.	
0750	616090 Construction Zone Attenuator	5.000 EACH	.		.	
0760	616122 Steel Protection Plate 5'X10'	10.000 EACH	.		.	
0770	617006 Remove Abandoned Traffic Signal Or Street Light Pole Foundat ion	8.000 EACH	.		.	
0780	617008 Furnish And Install Pcc Foundation For Traffic Signal Pole O r Pendant Post Street Light Pole	8.000 EACH	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0790	617010 Furnish And Install 3 Foot By 3 Foot Electrical Manhole	3.000 EACH	.		.	
0800	617012 Furnish And Install 4 Foot By 4 Foot Electrical Manhole	1.000 EACH	.		.	
0810	617014 Furnish And Install One 2 Inch Pvc Encased Electrical Conduit	35.000 LF	.		.	
0820	617016 Furnish And Install One 4 Inch Pvc Encased Electrical Conduit	95.000 LF	.		.	
0830	617018 Furnish And Install No. 10 Awg Stranded Wire	102.000 LF	.		.	
0840	617020 Furnish And Install No. 8 Awg Stranded Wire	268.000 LF	.		.	
0850	617022 Furnish And Install No. 6 Awg Stranded Wire	576.000 LF	.		.	
0860	617024 Furnish And Install Galvanized Steel Transformer Base	12.000 EACH	.		.	
0870	617026 Furnish And Install 28 Foot 6 Inch Tall Pendant Post Street Light Pole	2.000 EACH	.		.	
0880	617028 Furnish And Install Handbox	4.000 EACH	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0890	617030 Furnish And Install One 2 Inch And Two 4 Inch Pvc Encased El ectrical Conduits	22.000 LF	.		.	
0900	617032 Furnish And Install One 2 Inch And One 4 Inch Pvc Encased El ectrical Conduits	145.000 LF	.		.	
0910	617034 Furnish And Install Four 4 Inch Pvc Encased Electrical Condu its	237.000 LF	.		.	
0920	617038 Furnish And Install Pcc Foundation For Controller Cabinet	1.000 EACH	.		.	
0930	617040 Furnish Temporary, Portable, Concrete Base For Model 336-S A nd Model 336-Ss Traffic Signal Controller Cabinet	1.000 EACH	.		.	
0940	617042 Furnish Temporary, Portable, Concrete Base For 20 Foot Steel Traffic Signal Pole Mounted On A Transformer Base BASE FOR 20 FOOT STEEL TRAFFIC SIGNAL	8.000 EACH	.		.	
0950	617044 Relocate Any Temporary, Portable, Concrete Base	6.000 EACH	.		.	
0960	617046 Furnish And Install 20 Foot Tall Steel Traffic Signal Pole	14.000 EACH	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0970	617048 Furnish And Install 8 Foot Long Mast Arm With Clamp And Removable End Cap WITH CLAMP AND REMOVABLE END CAP	EACH 4.000
0980	617050 Furnish And Install 7 Conductor 14 Awg Stranded Electrical Traffic Signal Cable	LF 2467.000
0990	617054 Furnish And Install 12 Pair 19 Awg Underground Communication s Cable	LF 250.000
1000	617056 Furnish And Install 12 Pair 19 Awg Overhead Communications Cable	LF 4400.000
1010	617068 Furnish Red Ball Led Module	EACH 14.000
1020	617070 Furnish Yellow Ball Led Module	EACH 14.000
1030	617072 Furnish Green Ball Led Module	EACH 14.000
1040	617084 Furnish 12 Inch Overlay Lunar White Walking Person And Portland Orange Raised Hand Led Module	EACH 8.000
1050	617086 Furnish 12 Inch Portland Orange Countdown Led Module	EACH 8.000

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1060	617090 Furnish And Install 3 Section Conventional Traffic Signal Head On A Pole (All Lenses 12?) TRAFFIC SIGNAL HEAD ON MAST ARMS	EACH 14.000	.		.	
1070	617096 Furnish And Install 3 Section Conventional Traffic Signal Head On A Mast Arm (All Lenses 12?) TRAFFIC SIGNAL HEAD ON MAST ARMS	EACH 4.000	.		.	
1080	617114 Furnish And Install 2 Section Conventional Pedestrian Signal Head On A Pole (12?)	EACH 8.000	.		.	
1090	617124 Furnish And Install Traffic Signal Controller And Cabinet	EACH 1.000	.		.	
1100	617126 Remove Abandoned Traffic Signal Controller Cabinet Foundation	EACH 1.000	.		.	
1110	617128 Remove Street Light Pole And Street Light Equipment	EACH 2.000	.		.	
1120	617132 Remove Traffic Signal Controller And Cabinet	EACH 1.000	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1130	618148 Furnish and Install 6-4" Schedule 40 Rigid PVC Conduits (duct bank)	2500.000 LF	.		.	
1140	618356 Furnish and Install #6 Tri-Plex Overhead Cable	150.000 LF	.		.	
1150	618624 Furnish and Install Wood Pole, 35 ft. Height or Less	4.000 EACH	.		.	
1160	618630 Remove Wood Pole 35 ft. Height or less	2.000 EACH	.		.	
1170	618668 Remove arm from wood pole up to 8 ft. in Length	22.000 EACH	.		.	
1180	618676 Furnish and Install 8 ft. Arm on Wood Pole	28.000 EACH	.		.	
1190	618720 Remove Luminaire from Wood Pole	22.000 EACH	.		.	
1200	618760 Furnish and Install 250 Watt HPS Tear Drop Fixture	28.000 EACH	.		.	
1210	618992 ELECTRICAL WORK SPECIAL ITEM -EACH- REMOVE TRAFFIC SIGNAL POLE AND TRAFIC SIGNAL EQUIPMENT ITEM 617 130	1.000 EACH	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1220	618992 ELECTRICAL WORK SPECIAL ITEM -EACH- REMOVE TRAFFIC SIGNAL WOOD POLE AND TRAF IC SIGNAL EQUIPMENT ITEM 617 134	EACH 1.000
1230	618999 Payment to PEPCO for Connection, Disconnection, Inspection CONNECTION AND DISCONNECTION OF POWER	LUMP	LUMP			10000.00
1240	620014 Traffic Sign Panels	SF 156.000
1250	620032 Remove Existing Ground Mounted Sign	SF 10.000
1260	620036 Reset Guide Sign Panel	SF 20.000
1270	620040 Federal Aid Project Sign	EACH 2.000
1280	620991 Traffic Signing Special Item - LF - STEEL SIGN POST, ITEM 620 005	LF 900.000
1290	624002 Engineer's Field Facilities	LUMP	LUMP			.
1300	625002 Field Layout	LUMP	LUMP			.

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2007B0137

PROJECT(S): STP-1113 (028)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1310	628002 Erosion and Sediment Control	LUMP	LUMP			.
1320	703002 PCC Footing	95.000 CY		.		.
1330	703006 PCC Pier-Abutment-Wall	100.000 CY		.		.
1340	704004 Epoxy Coated Reinforcement Bars	22000.000 LBS		.		.
1350	708002 Stone Masonry, Class A	489.000 CF		.		.
	SECTION 0001 TOTAL					.
	TOTAL BID					.