TABLE OF CONTENTS

SP NO.	TITLE	PAGE NO.
1	SCOPE OF WORK	3
2	CONTRACT TYPE	5
3	DISPUTES	5
4	PRE-AWARD APPROVAL	8
5	AWARD OR REJECTION	8
6	COORDINATION WITH OTHERS	8
7	COORDINATION OF WORK BETWEEN JURISDICTIONS	9
8	CONTRACTOR IDENTIFICATION	9
9	PRE-BID CONFERENCE	10
10	APPLICABLE WAGE DECISION/WAGE RATES - DC	10
11	APPLICABLE WAGE DECISION/WAGE RATES - MD	11
12	PROTESTS	11
13	CONTRACT ADMINISTRATION DATA	11
14	SUBCONTRACTING	14
15	SHOP AND WORKING DRAWINGS	15
16	CONSTRUCTION COMPLETION TIME	17
17	WORK HOURS	17
18	NIGHT WORK	18
19	MOWING, TRIMMING AND LANDSCAPE MAINTENANCE	18
20	CONSTRUCTION SCHEDULING	19
21	WORK AND STORAGE SPACE	19
22	PROJECT SECURITY	20
23	TITLE VI ASSURANCE	20
24	SALVAGED MATERIALS	21
25	OPTIONAL MATERIALS	21
26	EXISTING FEATURES	22
27	DEPARTMENTAL ORDER NO. 2001-01	22
28	PUBLIC SAFETY AND CONVENIENCE	24
29	INSURANCE	24
30	VALUE ENGINEERING CHANGE PROPOSALS	24A
31	PROTECTION OF EXISTING TRAIL	24
32	UTILITY STATUS	25
33	RIGHT-OF-WAY STATUS	26
34	PERMIT STATUS	26
35	TIME-OF-YEAR RESTRICTIONS	27
36	OCCUPYING WETLANDS	27
37	ADDITIONAL NATIONAL PARK SERVICE REQUIREMENTS	28

38 EMPLOYEE TRAINING: ITEM 000 003 35
39 AS-BUILT DRAWINGS: ITEM 108 004 35
40 MAINTENANCE OF RAILROAD TRAFFIC: ITEM 108 999 35
41 CLEARING AND GRUBBING: ITEM 201 002 44
42 REMOVE EXISTING CHAIN LINK FENCE: ITEM 201 002 45
43 COMMON EXCAVATION: ITEM 202 002 45
44 MANAGEMENT AND DISPOSAL OF EXCAVATED SOIL AND CONTAMINATED WATER: ITEMS 202 996 THRU 202 999 45
45 BORROW EMBANKMENT FILL: ITEM 204 004 51
46 STRUCTURE EXCAVATION: ITEM 205 002 52
47 AGGREGATE TOPSOIL MIX: ITEM 209 991 52
48 STONE DUST: ITEM 209 992 53
49 PROGRESS PHOTOGRAPHS: ITEM 308 002 53
50 TRENCH GRATE: ITEM 311 998 54
51 CLEAN STORM DRAIN STRUCTURE: ITEM 311 999 54
52 CLEAN STORM DRAIN PIPE: ITEM 314 998 55
53 LEVEL SPREADERS: ITEM 314 999 55
54 FOAMED ASPHALT 55
55 HOT-MIX ASPHALT PAVEMENT (HMA): ITEM 402 002, 402 010 55
56 ASPHALT BIKE PATH: ITEMS 402 002 AND 402 010 56
57 STONE VENEER SEAT WALL: ITEM 602 999 56
58 DRIVE ANCHORS FOR FENCING: ITEM 607 014 57
59 ACCESS GATES: ITEMS 607 997 AND 607 998 57
60 ORNAMENTAL SAFETY FENCE: ITEM 607 999 58
61 INTEGRAL COLOR CONCRETE, STAMP, TEXTURE, FORMLINER 6" DEPTH: ITEM 608 999 58
62 PCC WHEELCHAIR/BICYCLE RAMP: ITEMS 609 200, 609 202 62
63 PARK BENCHES: ITEM 611 094 64
64 TREE SIZES AT PLANTING 65
65 INVASIVE SPECIES MANAGEMENT: ITEM 611 127 65
66 SEEDING: ITEMS 611 181 THRU 611 184 70
67 SHREDDED LEAF MOLD: ITEM 611 185 73
68 INSTALLATION OF TREE AND SHRUB SLEEVES: ITEMS 611 187, 611 188 74
69 GROUND MOUNT HOOP BICYCLE RACK: ITEM 611 189 75
70 SOIL AMENDMENT AND RESTORATION FOR REFORESTATION AREAS: ITEM 611 190 76
71 SUPPLEMENTAL TREE PROTECTION: ITEMS 611 192 THRU 611 199 79
72 SHREDDED HARDWOOD MULCH 82
73 MAINTENANCE OF TRAFFIC: ITEM 616 001 83
74 ORANGE PAVEMENT MARKINGS: ITEM 616 061 85
75 THERMOPLASTIC PAVEMENT MARKING, TRAIL CROSSWALK: ITEM 616 987 86
76 THERMOPLASTIC PAVEMENT MARKING SYMBOL: ITEM 616 988 AND 616 989 86

77 THERMOPLASTIC PAVEMENT MARKING, 24 INCH: ITEM 616 990 86
78 ELECTRICAL WORK: ITEM 618 002 87
79 RIGID GALVANIZED STEEL CONDUIT: ITEMS 618 982, 618 983, 618 984 92
80 PVC CONDUIT: ITEMS 618 100, 618 072 93
81 MANHOLE: ITEM 618 016 94
82 ELECTRICAL CABLES: ITEMS 618 190, 618 196, 618 252, 618 256 95
83 GROUND RODS: ITEM 618 910 96
84 GROUND WIRES: ITEMS 618 292, 618 298, 618 310 97
85 FURNISH AND INSTALL FIFTEEN (15) INCH B.C. STREET LIGHT FOUNDATION: ITEM 618 394 98
86 FURNISH AND INSTALL FIFTEEN (15) INCH B.C. STEEL TRANSFORMER BASE: ITEM 618 436 99
87 FURNISH AND INSTALL LED UNDERPASS LUMINAIRE: ITEM 618 986 100
88 FURNISH AND INSTALL STREETLIGHT CIRCUIT CONTROL CABINET AND CONTROLLER: ITEM 618 987 101
89 FURNISH AND INSTALL FOUNDATION FOR STREETLIGHT CIRCUIT CONTROL CABINET: ITEM 618 988 107
90 FURNISH AND INSTALL 20-FOOT STEEL POLE WITH PHOTOCELL: ITEM 618 989 108
91 FURNISH AND INSTALL METAL NEMA 4 JUNCTION BOXES: ITEM 618 990 110
92 PAYMENT TO PEPCO FOR CONNECTION AND DISCONNECTION OF SERVICE TO STREETLIGHTS: ITEM 618 998 111
93 UNIGUIDE SIGNING: ITEMS 620 888 THRU 620 899 111
94 FIELD LAYOUT: ITEM 625 002 117
95 TURBIDITY CURTAIN: ITEM 628 002 117
96 EROSION AND SEDIMENT CONTROL: ITEM 628 002 119
97 PREFABRICATED PEDESTRIAN BRIDGES: ITEM 700 996 THRU 700 999 120
98 HELICAL SCREW PILE FOUNDATION: ITEMS 701 004, 701 996 THRU 701 999 129
99 CAISSON (NO BELL): ITEM 701 062, 701 995 138
100 COATING OF STEEL SHEET PILES: ITEM 701 994 153
101 STEEL SHEET PILE WALL: ITEM 701 994 156
102 PRECAST CONCRETE SLABS: ITEM 703 008 160
103 EXTENSIONS BRIDGE RAILING: ITEM 709 998 162
104 42-INCH COMBINATION TIMBER AND STEEL RAILING: ITEM 709 999 162
105 ROUGH CARPENTRY: ITEM 709 999 163
106 GEOGRID: ITEM 713 997, 713 998 166
107 METALIZATION OF FERROUS METAL SURFACES 167
108 TEMPORARY BERTHING PIER 169A
109 BARGE OPERATION 170
110 PEPCO APPROVED METER AND SAFETY SWITCH: ITEM 618 985 171
111 REPAIR ELECTRICAL MANHOLE: ITEM 618 052 172

APPENDICES:

APPENDIX A - SUBCONTRACTOR APPROVAL REQUEST FORM (1 PAGE)

APPENDIX B - EQUAL EMPLOYMENT OPPORTUNITY/AFFIRMATIVE ACTION REQUIREMENTS (2 PAGES)

APPENDIX C - MONTHLY EQUAL EMPLOYMENT OPPORTUNITY REPORT (2 PAGES)

APPENDIX D - SPECIFIC EEO RESPONSIBILITIES (5 PAGES)

APPENDIX E - FHWA 1273 REQUIRED CONTRACT PROVISIONS (12 PAGES)

APPENDIX F - TRAINING SPECIAL PROVISIONS (2 PAGES)

APPENDIX G - EMPLOYEE TRAINING REQUIREMENTS (2 PAGES)

APPENDIX H - DEPARTMENT OF LABOR GENERAL WAGE DECISION NO. DC130001 (12 PAGES)

APPENDIX I - PARTICIPATION BY DISADVANTAGED BUSINESS ENTERPRISE AND NON-DISADVANTAGED BUSINESS ENTERPRISE FIRMS (3 PAGES)

APPENDIX J - CONSTRUCTION ZONE TRAFFIC CONTROL DEVICE INSPECTION LOG (2 PAGES)

APPENDIX K - STANDARD TRAFFIC CONTROL DETAILS (14 PAGES)

APPENDIX L - ARRA PROJECT SIGN DETAILS

APPENDIX M - MDOT GENERAL PROVISIONS (79 PAGES)

APPENDIX N - SUPPLEMENT TO MDOT GENERAL PROVISIONS (34 PAGES)

APPENDIX O - AMTRAK INSURANCE REQUIREMENTS (4 PAGES)

APPENDIX P - DRAFT AMTRAK CONSTRUCTION PHASE AGREEMENT (36 PAGES)

APPENDIX Q - DRAFT CONTRACTOR REFERENCES IN THE AMTRAK LEASE AGREEMENT (7 PAGES)

APPENDIX R - SCHEDULE OF QUANTITIES BY JURISDICTION (8 PAGES)

APPENDIX S - TREE TABLE (35 PAGES)

APPENDIX T - PERMITS (99 PAGES)