

<b>AMENDMENT OF SOLICITATION / MODIFICATION OF CONTRACT</b>			1. Contract Number DCKA-2014-B-0085	Page of Pages 1   28	
2. Amendment/Modification Number Amd 5	3. Effective Date See 16C	4. Requisition/Purchase Request No.	5. Solicitation Caption <b>Klingle Valley Trail</b>		
6. Issued by: District Department of Transportation OCP 55 M Street, SE Suite 700 Washington, DC 20003		Code	7. Administered by (If other than line 6) District Department of Transportation IPMA 55 M Street, SE 4 <sup>th</sup> floor Washington, DC		
8. Name and Address of Contractor (No. street, city, county, state and zip code)		Code	Facility	9A. Amendment of Solicitation No. DCKA-2014-B-0085	
				X	9B. Dated (See Item 11) 9/19/2014
					10A. Modification of Contractor/Order No.
					10B. Dated (See Item 13)
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS					
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in item 14. The hour and date specified for receipt of Offers <input type="checkbox"/> is extended. <input type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>2</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) BY separate letter or fax which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such may be made by letter or fax, provided each letter or telegram makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.					
12. Accounting and Appropriation Data (If Required):					
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14					
A. This change order is issued pursuant to (Specify Authority): The changes set forth in Item 14 are made in the contract/order no. in item 10A.					
B. The above numbered contract/order is modified to reflect the administrative changes (such as changes in paying office, appropriation data etc.) set forth in item 14, pursuant to the authority of 27 DCMR, Chapter 36, Section 3601.2.					
C. This supplemental agreement is entered into pursuant to authority of:					
D. Other (Specify type of modification and authority) Adding additional scope and increasing the amount of the original contract					
E. IMPORTANT: Contractor <input type="checkbox"/> is not <input checked="" type="checkbox"/> is required to sign this document and return <u>1</u> copies to the issuing office.					
14. Description of Amendment/Modification (Organized by UCF Section headings, including solicitation/contract subject matter where feasible.)  <b>Solicitation No.: DCKA-2014-B-0085:</b>  1) This solicitation is hereby amended with a revised Pay Item schedule. 2) Attached are the responses for the final series of inquiries.					
Except as provided herein, all terms and conditions of the document referenced in item (9A or 10A) remain unchanged and in full force and effect.					
15A. Name and Title of Signer (Type or print)		16A. Courtney Lattimore Deputy Chief Contracting Officer			
15B. Name of Contractor  (Signature)	15C. Date Signed	15B. District of Columbia  (Signature of Contracting Officer)	16C. Date Signed 11/8/15		

SCHEDULE OF ITEMS

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 ROADWAY CONS AND STREAM RESTORATION						
0010	000003 Employee Training	500.000				
		HR				
0020	000103 Materials Special Item - CY -	618.000				
	000113-PLANT BED SOIL	CY				
0030	000103 Materials Special Item - CY -	124.000				
	000115-CLASS II RIPRAP	CY				
0040	000111 Materials Special Item - SY - CLASS I	690.000				
	RIPRAP	SY				
0050	000511 Unassigned Special Item -LS -	LUMP	LUMP			30000.00
	000021-NPS UNIGUIDE SIGN DESIGN AND FABRICATION					
0060	000511 Unassigned Special Item -LS -	LUMP	LUMP			1000.00
	000519-WMATA INSPECTION					
0070	000511 Unassigned Special Item -LS -	LUMP	LUMP			3500.00
	000521-WMATA REAL ESTATE FEE					
0080	000511 Unassigned Special Item -LS -	LUMP	LUMP			7500.00
	000523-WMATA CONTINGENCY					
0090	000511 Unassigned Special Item -LS -	LUMP	LUMP			20000.00
	000525-PARTNERING					

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168 (013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	108002 Progress Photographs	LUMP	LUMP			
0105	108004 As-Built Drawings	LUMP	LUMP			
0110	200003 Earthwork and Excavation Special Item - CY - 200013-CHANNEL EXCAVATION	CY	954.000			
0120	200003 Earthwork and Excavation Special Item - CY - 200015-SALVAGED STREAMBED MATERIAL	CY	718.000			
0130	201991 Clear and Grub Special Item - LS - 201001-STREAM RESTORATION	LUMP	LUMP			
0140	201991 Clear and Grub Special Item - LS - 201005-TRAIL CONSTRUCTION	LUMP	LUMP			
0150	202002 Common Excavation	CY	1413.000			
0160	202004 Hard Surface Pavement Excavation	CY	4075.000			
0170	202991 Roadway Excavation Special Item - CY - REMOVAL OF SOFT AND UNSUITABLE MATERIAL	CY	283.000			
0180	204002 Embankment Fill	CY	983.000			

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0190	204004 Borrow Embankment Fill	 2544.000  CY				
0200	205004 Structure Hard Surface Excavation	 320.000  CY				
0210	205008 Demolition REMOVAL OF EXISTING MASONRY RETAINING WALLS	 115.000  CY				
0220	206002 Structure Backfill 206001-STREAM RESTORATION	 847.000  CY				
0230	206002 Structure Backfill 206003-RETAINING WALL	 130.000  CY				
0240	207002 Trench Excavation and Backfill	 200.000  CY				
0250	207004 Trench Undercut Excavation	 25.000  CY				
0260	207006 Gravel for Trench Undercut	 25.000  CY				
0270	207008 Borrow Trench Backfill	 200.000  CY				
0280	209002 Aggregate Base Course	 635.000  CY				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0290	209991 Aggregate Base Course Special Item -CY- 209001-AGGREGATE BASE COURSE FOR LID #57 STONE	1421.000 CY				
0300	209991 Aggregate Base Course Special Item -CY- 209003-AGGREGATE BASE COURSE FOR LID #8 STONE	736.000 CY				
0310	209991 Aggregate Base Course Special Item -CY- 209005-SANDY GRAVEL FILTER LAYER FOR LID	34.000 CY				
0320	212002 Test Pit	52.000 EACH				
0330	300004 Water and Sewer Service Special Item-EACH- 300013-BEEHIVE GRATE	4.000 EACH				
0340	300004 Water and Sewer Service Special Item-EACH- 300015-TYPE K INLET	3.000 EACH				
0350	300004 Water and Sewer Service Special Item-EACH- 300017-DUAL THROAT WATER QUALITY BASIN	5.000 EACH				
0360	300004 Water and Sewer Service Special Item-EACH- 300019-CLEAN EXISTING CATCH BASIN	1.000 EACH				

SCHEDULE OF ITEMS

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0370	300005 Water and Sewer Service Special Item-LF - CLEAN EXISTING STORM DRAIN PIPE (ANY SIZE)	100.000 LF				
0380	309002 Sewer Manhole on Sewer 48 Inch and Less Dia.	11.000 VLF				
0390	310002 Standard Basin	2.000 EACH				
0400	311002 Adjust Sewer-Water-Utility Manhole Frame	21.000 EACH				
0410	311993 Adjust, Rebuild&Replace Manhole&Catchbasin-Special Item -CY- REINFORCED CONCRETE PIPE COLLAR	0.400 CY				
0420	312006 Replace Standard Basin Top	2.000 EACH				
0430	314044 PCC Pipe, Class IV, Gasket, 12 Inch	56.000 LF				
0440	314046 PCC Pipe, Class IV, Gasket, 15 Inch	235.000 LF				
0450	314048 PCC Pipe, Class IV, Gasket, 18 Inch	200.000 LF				
0460	314060 PCC Pipe, Class IV, Gasket, 36 Inch	128.000 LF				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0470	314991 Sewer Pipe   Special Item - LF -   HORIZ. ELLIPTICAL RCP .   PIPE, CLASS IV WITH   RUBBER GASKETS, 24" X   38"	     LF   	59.000			
0480	400009 Asphalt   Construction Special   Item -TON -   400011-POROUS ASPHALT   PAVEMENT SURFACE COURSE	     TON   	210.000			
0490	400009 Asphalt   Construction Special   Item -TON -   400013-POROUS ASPHALT   PAVEMENT BASE COURSE	     TON   	421.000			
0500	402002 Superpave Base   Course, 19 mm PG 64-22	   TON	154.000			
0510	402012 Sperrpave Surface   Course, 12.5 mm   402001-PG 64-22	   TON	77.000			
0520	402012 Sperrpave Surface   Course, 12.5 mm   402003-PG 70-22	   TON	98.000			
0530	403002 Tack Coat	   SY	724.000			
0540	501002 Reinforced PCC   Pavement	   CY	4.000			
0550	505024 Replace   Driveway-Alley Entrance,   7 Inch	   SY	32.000			

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0560	600004 Incidental Construction Special Item - CY - BIORETENTION SOIL	291.000 CY				
0570	600006 Incidental Construction Special Item - EACH - 600021-UNDERDRAIN CLEANOUT / TRAIL	28.000 EACH				
0580	600006 Incidental Construction Special Item - EACH - 600023-UNDERDRAIN CLEANOUT / BIO SWALE OR BIORETENTION	16.000 EACH				
0590	600006 Incidental Construction Special Item - EACH - 600025-FURNISH AND INSTALL 35 WATT LED MODERN POST-TOP LUMINAIRE	52.000 EACH				
0600	600006 Incidental Construction Special Item - EACH - 600027-ROCK CHECK DAM, AASHTO #2 STONE	21.000 EACH				
0610	600009 Incidental Construction Special Item - LF - 600033-6 X 6 TIMBER EDGING	255.000 LF				
0620	600014 Incidental Construction Special Item - SY - 600017-RIPARIAN BUFFER SEED MIX	5478.000 SY				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0630	600014 Incidental Construction Special Item - SY - 600033-GEOTEXTILE FOR STORMWATER MANAGEMENT	2971.000 SY				
0640	600014 Incidental Construction Special Item - SY - 600035-GEOTEXTILE, CLASS ST	708.000 SY				
0650	600014 Incidental Construction Special Item - SY - 600037-3/8" PVC SHEET TYPE I CHECK DAMS	189.000 SY				
0660	602002 PCC Footing (Minor)	38.300 CY				
0670	602006 Stone Masonry Wall	32.700 CY				
0680	602012 Special PCC Coping SPECIAL PCC COPING	28.000 CY				
0690	603002 Underdrain Pipe, 4 Inch	4060.000 LF				
0700	603004 Underdrain Pipe, 6 Inch	188.000 LF				
0710	605991 Steel Guiderails Special Item - EACH WEATHERING STEEL W-BEAM GUIDERAIL END SECTION ANCHOR	2.000 EACH				

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0720	605993 Steel Guiderails Special Item - LF - WEATHERING STEEL W-BEAM GUIDERAIL, 8-FT POST	94.000 LF				
0730	606002 Pavement Profiling (Milling)	724.000 SY				
0740	607014 Vinyl Clad Chain Link Fence, 6 Ft. Ht. BLACK	200.000 LF				
0750	607991 Misc. Fencing Special Item - LF - 607001-TREE PROTECTION FENCE	792.000 LF				
0760	607991 Misc. Fencing Special Item - LF - 607003-CONSTRUCTION FENCE	7090.000 LF				
0770	607991 Misc. Fencing Special Item - LF - 607005-METAL FENCE	241.000 LF				
0780	607991 Misc. Fencing Special Item - LF - 607007-WOODEN FENCE	1904.000 LF				
0790	608024 Brick Sidewalk on PCC Base BRICK BANDING	25.000 SY				
0800	608028 Block Sidewalk on PCC Base	314.000 SY				
0810	608992 Sidewalks & Driveway Special Item - SY - 608001-INSTALL BRICK PAVERS	222.000 SY				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0820	608992 Sidwalks & Driveway Special Item - SY - 608003-FURNISH AND INSTALL INSTALL BRICK PAVERS	62.000				
0830	609006 PCC Curb and Gutter, 13 to 15 Inch Depth	601.000				
0840	609012 PCC Circular Curb and Gutter, 13 to 15 Inch Depth	640.000				
0850	609016 PCC Curb, 13 to 15 Inch Depth	44.000				
0860	609020 PCC Circular Curb, 13 to 15 Inch Depth	27.000				
0870	609038 PCC Gutter, 7 to 10 Inch Depth x 12-24 Inch Width	27.000				
0880	609040 PCC Circular Curb for Alley-Drive Entrance	12.000				
0890	609068 Furnish and Set 8"x12" Granite Straight Curb	68.000				
0900	609072 Furnish and Set 8"x12" Granite Circular Curb, Radius 10-100 Ft.	9.000				
0910	609200 PCC Wheelchair/Bicycle Ramp - New Construction	3.000				

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0920	610002 Seed TEMPORARY SEED	5478.000 SY				
0930	610004 Seed with 4 Inch Topsoil	6012.000 SY				
0940	610014 Erosion Control Matting	361.000 SY				
0950	610060 Mulch 610001-TEMPORARY MULCH	5478.000 SY				
0960	610060 Mulch 610003-3" THICK TRIPLE SHREDDED HARDWOOD MULCH	1822.000 SY				
0970	610060 Mulch 610005-3" WOOD CHIPS	347.000 SY				
0980	611002 Remove Tree and Stump up to 6 Inch Dia.	31.000 EACH				
0990	611004 Remove Tree and Stump 6 to 12 Inch Dia.	43.000 EACH				
1000	611006 Remove Tree and Stump 12 to 18 Inch Dia.	16.000 EACH				
1010	611008 Remove Tree and Stump 18 to 24 Inch Dia.	6.000 EACH				
1020	611010 Remove Tree and Stump 24 to 30 Inch Dia.	3.000 EACH				

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1030	611012 Remove Tree and Stump 30 to 36 Inch Dia.	3.000 EACH	.	.	.	.
1040	611014 Remove Tree and Stump 36 to 42 Inch Dia.	2.000 EACH	.	.	.	.
1050	611024 Remove Tree 30 to 36 Inch Dia.	1.000 EACH	.	.	.	.
1060	611094 Park Benches SITE BENCH, VICTOR-STANLEY, CR-196, COLOR BLACK	12.000 EACH	.	.	.	.
1070	611104 Litter Baskets LITTER RECEPTACLE, VICTOR-STANLEY, SDDC-42, COLOR BLACK	2.000 EACH	.	.	.	.
1080	611285 Amelanchier canadensis (Shadblow Serviceberry) 5 - 6 Ft. Ht. , B&B	6.000 EACH	.	.	.	.
1090	611335 Betula nigra (River Birch) 2 1/2 - 3 Inch Cal., B&B	4.000 EACH	.	.	.	.
1100	611594 Kalmia latifolia (Mountain Laurel) 3 - 4 Ft. Ht., B&B	12.000 EACH	.	.	.	.
1110	611620 Lindera benzoin (Spicebush) 18 - 24 Inch Ht., B&B	14.000 EACH	.	.	.	.

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1120	611625 Liquidambar styraciflua (American Sweetgum) 2 - 2 1/2 Inch C al., B&B HAPDELL HAPPIDAZE SWEETGUM, 2.5" - 3.0" CALIPER, B&B	7.000 EACH				
1130	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611001-LIVE STAKE	2361.000 EACH				
1140	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611003-TUBELING	756.000 EACH				
1150	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611005-FERN PLUGS	504.000 EACH				
1160	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611007-DEER PROTECTION SLEEVE	148.000 EACH				
1170	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611009-DEER PROTECTION WIRE CAGE	55.000 EACH				
1180	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611011-ASIMINA TRILOBA, PAWPAW 1 INCH CAL. CG	18.000 EACH				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1190	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611013-MERTENSIA VIRGINICA (VIRGINIA BLUEBELLS) 1 GALLON	425.000 EACH				
1200	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611015-PODOPHYLLUM PELTATUM (MAYAPPLE) 1 GALLON	480.000 EACH				
1210	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611017-PANICUM CLANDESTINUM (DEER TONGUE GRASS) 1 GALLON	372.000 EACH				
1220	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611019-PANICUM VIRGATUM 'SHENANDOAH' (SWITCH GRASS), 1 GALLON	495.000 EACH				
1230	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611021-PERENNIAL, QUART SIZE	504.000 EACH				
1240	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611023-AMELANCHIER ARBOREA, DOWNY SERVICEBERRY, 3 FOOT HT., 2 GC	80.000 EACH				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1250	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611025-EUONYMUS AMERICANUS, AMERICAN EUONYMUS, 3 FOOT HT., 2 GC	80.000 EACH				
1260	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611027-BETULA NIGRA (RIVER BIRCH) 2 INCH CAL. , CG	20.000 EACH				
1270	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611029-CERCIS CANADENSIS (EASTERN REDBUD) 1 INCH CAL. CG	18.000 EACH				
1280	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611031-CORNUS FLORIDA (FLOWERING DOGWOOD) 2 INCH CAL., CG	18.000 EACH				
1290	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611033-FAGUS GRANDIFOLIA (AMERICAN BEECH) 2 INCH CAL., CG	18.000 EACH				
1300	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611035-ILEX OPACA (AMERICAN HOLLY) 2 INCH CAL., CG	19.000 EACH				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1310	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611037-LIRIODENDRON TULIPIFERA (TULIP POPLAR) 2 INCH CAL., CG	18.000 EACH				
1320	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611039-CARYA GLABRA (PIGNOT HICKORY) 2 INCH CAL., CG	18.000 EACH				
1330	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611041-QUERCUS RUBRA (NORTHERN RED OAK) 2 INCH CAL., CG	18.000 EACH				
1340	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611043-AMELANCHIER ARBOREA (DOWNY SERVICEBERRY), 6 FT. HT. B&B	7.000 EACH				
1350	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611045-TAXODIUM DISTICHUM (BALD CYRESS), 2.5" - 3.0" CALIPER, B&B	4.000 EACH				
1360	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611047-ARONIA MELANOCARPA 'AUTUMN MAGIC (AUTUMN MAGIC CHOKEBERRY), 3-4 FT. HT. C	62.000 EACH				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1370	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611049-CORNUS SERICEA 'FARROW' (FARROW RED TWIG DOGWOOD), 3-4 FT. HT. CONT.	50.000 EACH				
1380	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611051-ILEX GLABRA 'COMPACTA' (COMPACT INKBERRY), 3-4 FT. HT. CONT.	36.000 EACH				
1390	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611053-VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 4 FT. HT. CONT.	12.000 EACH				
1400	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611057-HYPERICUM CALYCINUM (ST. JOHNSWORT GROUND COVER), 2 IN. PLUG	2600.000 EACH				
1410	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611061-HAMMAMELIS VIRGINIANA (COMMON WITCH-HAZEL), 3 FOOT HT., 2 GC	80.000 EACH				
1420	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611063-ILEX VERTICILLATA (WINTERBERRY), 3 FOOT HT., 2 GC	78.000 EACH				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1430	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611065-NYSSA SYLVATICA 'WILDFIRE' (WILDF IRE BLACKGUM) 2.5"-3.0" CALIPER, B&B	3.000 EACH				
1440	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611067-PLATANUS OCCIDENTALIS (SYCAMORE) 2 INCH CAL., CG	20.000 EACH				
1450	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611071-ILEX VERTICILLATA 'RED SPRITE' (R ED SPRITE WINTERBERRY), 3-4 FT. HT. CONT	11.000 EACH				
1460	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611073-CAREX EBURNEA (BRISTLE-LEAF SEDGE), 1 QUART	1150.000 EACH				
1470	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611075-PANICUM VIRGATUM 'CHEYENNE' (SWITCH GRASS), 1 GALLON	35.000 EACH				
1480	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611077-KALMIA LATIFOLIA (MOUNTAIN LAUREL) 3 FOOT HT., 2 GC	80.000 EACH				

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1490	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611079-LINDERA BENZOIN (SPICEBUSH) 3 FOOT HT., 2 GC	80.000 EACH				
1500	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611081-NYSSA SYLVATICA (BLACKGUM) 2 INCH CAL., CG	18.000 EACH				
1510	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611083-VIBURNUM DENTATUM 'BLUE MUFFIN' ( BLUE MUFFIN VIBURNUM), 2-3 FT. HT. CONT.	26.000 EACH				
1520	611999 Tree, Shrub, Vine, & Ground Cover Special Item - EACH - 611085-CHASMANTHIUM LATIFOLIUM (WILD OATS), 1 GALLON	156.000 EACH				
1530	612002 Mobilization	LUMP	LUMP			
1540	616001 Maintenance of Highway Traffic	LUMP	LUMP			
1550	616006 Remove Lane Markings	53.000 SF				
1560	616008 Temporary Construction Sign Supports	10.000 EACH				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1570	616012 Construction Warning and Detour Signs	137.000 SF	.		.	
1580	616024 Type III PVC Barricade	6.000 EACH	.		.	
1590	616028 Traffic Drums	34.000 EACH	.		.	
1600	616040 Thermoplastic Pavement Marking, 4 Inch	1629.000 LF	.		.	
1610	616044 Thermoplastic Pavement Marking, 6 Inch	328.000 LF	.		.	
1620	616050 Thermoplastic Pavement Marking, 12 Inch	107.000 LF	.		.	
1630	617010 Furnish And Install 3 Foot By 3 Foot Electrical Manhole	18.000 EACH	.		.	
1640	617014 Furnish And Install One 2 Inch Pvc Encased Electrical Conduit	2090.000 LF	.		.	
1650	617014 Furnish And Install One 2 Inch Pvc Encased Electrical Conduit	3820.000 LF	.		.	
1660	617016 Furnish And Install One 4 Inch Pvc Encased Electrical Conduit	590.000 LF	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1670	618190 Furnish and Install #10 Stranded Wire	5000.000 LF	.	.	.	.
1680	618220 Furnish and Install #2 Stranded Wire	775.000 LF	.	.	.	.
1690	618232 Furnish and Install #0 Stranded Wire	7770.000 LF	.	.	.	.
1700	618250 Furnish and Install #0000 Stranded Wire	2320.000 LF	.	.	.	.
1710	618292 Furnish and Install #8 Stranded Ground Wire	2620.000 LF	.	.	.	.
1720	618298 Furnish and Install #6 Stranded Ground Wire	2640.000 LF	.	.	.	.
1730	618394 Furnish and Install 15" B.C. Street Light Foundation	52.000 EACH	.	.	.	.
1740	618486 Furnish and Install #16 Cast Iron Pole	52.000 EACH	.	.	.	.
1750	618888 Furnish and Install 4" PVC Rigid U-Guard on Wood Pole	30.000 LF	.	.	.	.
1760	618999 Payment to PEPCO for Connection, Disconnection, Inspection PAYMENT TO PEPCO FOR CONNECTION TO STREETLIGHT	LUMP	LUMP	.	30000.00	.

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1770	620014 Traffic Sign Panels	137.000 SF	.	.	.	.
1780	620032 Remove Existing Ground Mounted Sign	18.000 SF	.	.	.	.
1790	620040 Federal Aid Project Sign	2.000 EACH	.	.	.	.
1800	620993 Traffic Signing Special Item - EACH - 620001-NPS UNIGUIDE STANDARD UPRIGHT SIGN INSTALLATION	2.000 EACH	.	.	.	.
1810	620993 Traffic Signing Special Item - EACH - 620003-NPS UNIGUIDE STANDARD SIGN / TRAILSIDE SIGN INSTALLATION	1.000 EACH	.	.	.	.
1820	620993 Traffic Signing Special Item - EACH - 620005-U-CHANNEL SIGN POSTS	20.000 EACH	.	.	.	.
1830	624002 Engineer's Field Facilities	LUMP	LUMP	.	.	.
1840	625002 Field Layout	LUMP	LUMP	.	.	.
1850	628002 Erosion and Sediment Control	LUMP	LUMP	.	.	.

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1860	628991 Erosion and Sediment Control Special Item - LS - MAINTENANCE OF STREAM FLOW	LUMP	LUMP			
1870	700002 Structures Construction Special Item - CY - CLAY CHANNEL BLOCK	27.000 CY				
1880	700004 Structures Construction Special Item - EACH - 700015-STEP POOL STRUCTURE	26.000 EACH				
1890	700004 Structures Construction Special Item - EACH - 700017-RIFFLE GRADE CONTROL	3.000 EACH				
1900	700004 Structures Construction Special Item - EACH - 700019-OUTFALL STABILIZATION	1.000 EACH				
1910	700004 Structures Construction Special Item - EACH - 700021-ROCK CASCADE WITH BOULDER CLUSTER	1.000 EACH				
1920	700004 Structures Construction Special Item - EACH - 700023-LOG PLACEMENT	6.000 EACH				
1930	700005 Structures Construction Special Item - LF - 700025-STONE TOE PROTECTION	1688.000 LF				

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2014B0085

PROJECT(S): STP-4168(013)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1940	700005 Structures Construction Special Item - LF - 700027-IMBRICATED RIPRAP WALL	107.000 LF				
1950	700010 Structures Construction Special Item - SY - FABRIC ENCAPSULATED SOIL LIFTS	1089.000 SY				
1960	700011 Structures Construction Special Item - TON - BOULDER PLACEMENT	126.000 TON				
1970	703002 PCC Footing FOOTING FOR MASONRY RETAINING WALL	30.000 CY				
1980	708004 Stone Masonry, Class B	2800.000 CF				
1990	708011 Reset Stone Masonry	145.000 CF				
2000	708013 Repoint Stone Masonry	4500.000 LF				
2010	711004 Wall Perforated Drain Pipe	105.000 LF				
2020	711008 Wall Drain Connect Pipe	90.000 LF				
	SECTION 0001 TOTAL					
	TOTAL BID					

# ATTACHMENT

Kingle Valley Trail  
Questions & Clarifications

Page	Document	Section	Comment/Question/Clarification	Comments/Disposition
3	Special Provisions	6. Coordination with Others	Special provision states that the contractor is to take into consideration that other work will be on-going within the project area and DOT/District assumes no liability for contract delays or cost from performance or non performance of others. Please advise on what projects in particular may or will be on-going during the contract time for this project so we can tentatively estimate any potential cost associated with these activities.	Washington Gas will be relocating a 8" gas main throughout the project area. Coordination with archaeological investigation work will also be required during the project. DOT is not currently aware of other adjacent projects that would impact this contract.
5	Special Provisions	8. Applicable Wage Decision/Wage Rates	Please confirm that Paving and Incidental grading rates are applicable for this project and not Heavy or Highway rates.	Paving and incidental grading rates are applicable
5	Special Provisions	8. Applicable Wage Decision/Wage Rates	The General Wage Decision No. DC140002 01/31/2014 DC2 has since been modified. Please confirm if this particular wage scale is correct as the wage included in the contract documents is DC140001 08/29/2014 DC1	Correct General Wage Decision No. is DC140001 11/7/2014 (see amendment #3)
36	Special Provisions	32. Contract Time	The special provision states "The Contractor shall start work on the date specified in a written Notice to Proceed issued by the Contracting Officer and shall thereafter complete the work within the number of consecutive calendar days provided by the contractor on the "Bid Summary" form found in the Bid Forms and Proposal of this invitation. If this item is for partnering, please provide the stipulated allowance for this item." Please provide this form for submission.	DDOT to issue contract time with amendment 3.
47	Special Provisions	45. WMAVA Adjacent Construction	Please confirm that the WMAVA insurance and monitoring are inclusive of three pay items 000 519 WMAVA INSPECTION, 000 521 WMAVA REAL ESTATE FEE, 000 523 WMAVA CONTINGENCY	Pay items 000 519 WMAVA INSPECTION and 000 523 WMAVA CONTINGENCY are contingencies set-up for inspection and insurance, respectively. These contingencies are estimates and actual costs may vary.
53	Special Provisions	51. Clearing & Grubbing - Trail Construction	The chart states English Ivy Removal and the quantity and unit is 5 and Day respectively. Please provide the correct unit for this item.	This is just an estimated time for the removal of English Ivy. This item shall be paid for under Clearing and Grubbing - Trail Construction.
53	Special Provisions	52. Common Excavation	Special provisions state that the common excavation includes removal of sidewalks, driveways, and other pavement as shown on the plans. Please advise if this is correct as this inclusive of pay item 202 004 Hard Surface Pavement Excavation	Removed last paragraph of SP 52, Common Excavation.
5h, 005 of 243	Drawings Bid Forms & Proposal	Summary of Quantities Schedule of Items	Summary of Quantities state the Common Excavation to be 1,413 CY while the schedule of items has Common Excavation listed with 4,380 CY. Please advise which quantity is correct.	The Summary of Quantities and schedule of items have been revised
54	Special Provisions	53. Removal of Soft and Unsuitable Material	Special provision states to replace the unsuitable material with Geosynthetic Stabilized Subgrade using Graded Aggregate Base, Item 209 002. Item 209 002 is Graded Aggregate Base and this work should be paid under DDOT item 213 002 Geosynthetic Stabilized Subgrade using Graded Aggregate Base. Please provide the proper item in the schedule of items.	The special provision is incorrect and has been updated. Areas where unsuitable material has been removed should be replaced with material meeting the requirements of Embankment Fill or Borrow Embankment Fill.
67	Special Provisions	(E)Submittals	Special provisions state that the contractor is to provide with its bid In-Situ Pavement test results for the projects referenced for porous asphalt. Are these test results required for all projects referenced and will DDOT allow only the test results for the most current project. Some test results may not be readily available for the projects referenced by asphalt paving subcontractors.	Bidders shall not consider the In-situ test results a requirement; however, any available information provided by the bidder will be considered favorably in the selection process.

176	Special Provisions	114. Reset Stone Masonry	Special provisions states that this item is to be paid by the CY Item 708 001 Reset Stone Masonry on the schedule of items has the units listed as CF. Please advise which unit is correct.	This item is in CF and the Special Provisions have been revised.
Appendix G	Appendix G	Participation by DBE and Non-DBE Firms	Please confirm that there is no DBE goal/requirement for this particular project as the amount is blank in the solicitation.	7% goal per office of civil rights
Sh. 103 of 243	Drawings	Trail Profile	Please provide a typical sections for the proposed trail at Sta. 201 +.00 as the trail profile encounters an existing 51" storm pipe.	See Sheet 087 of 243 - Typical Sections and CS-08 - Trail Cross Sections. Contractor shall confirm top elevation of ex. 51" storm drain during construction.
<b>12/5/2014</b>				
General	Drawings	Stream Cross Sections	In the event there is a discrepancy between the plan view and the cross section, which detail takes precedence?	The Cross Sections take precedence.
Items 30 & 40	Bid Forms	Summary of Quantities Schedule of Items	Bid line items #030 & 040 Class II Riprap and Class I Riprap units of measure are CY & SY, which is correct? The M&P section for Riprap say measure and payment will be made by the SY.	Class II Riprap for use at Stream Stations 0+00 to 0+51 was considered a Materials Special Item and estimated as a volume since it will be combined with salvaged riprap from that area.
Item 180 & 190	Bid Forms & Special Provisions	General	Is there a special provision for bid line items 180 & 190, embankment fill and embankment borrow?	No, there is not a special item for embankment fill or embankment borrow.
Item 220	Bid Forms & Special Provisions	Structure Backfill	Bid line item 220, structure backfill: The SP's reference section 206.04, what is 206.04? Is this natural channel backfill?	Sections 206.01 through 206.04 are from the DDOT 2009 Standard Specifications for Highways and Structures (pages 136-137), and describe the Structure Backfill item. It is not natural channel backfill.
Sh. 195 of 243	Drawings	Cross Sections	Profile page 195 of 243 at station 00 + 75 does not show stone toe. Should stone toe be shown or does the ESL extend out of the distance shown on the profiler? Or is the plan view on page 34 of 245 correct?	It is intended that the stone toe will start and stop on either side of the clay channel block and other in-stream structures (please refer to #10 on page 170 of the special provision for stone toe). The cross section at station 00+75 does not show stone toe because it is located at the clay channel block.
Sh. 40 of 243	Drawing	Stone Toe	Stone toes as shown on profile pages scales to 3' in height but the detail on page 40 of 243 shows a minimum of 4' height. Which is correct?	A minimum of 3 feet in height is correct, as shown on the cross sections and specified in stone toe special provision. The stone toe details on pages 40 and 42 are incorrect and should read 3' minimum.
Sh. 36 of 243	Drawing	Stone Toe	Sheet 036 shows a stone toe along the north side of the stream around Station 204+50. There is an existing retaining wall there. Does that wall come out or does the stone toe go in front of the wall?	The stone toe shall be placed in front of the wall to protect the wall footer. Please refer to the "Stone Toe at Retaining Wall" detail on sheet 044 of 243, as well as cross sections 14+25, 14+50, and 14+75 on sheets 212 and 213.
Sh. 36 of 243	Drawing	Boulder Placement	Sheet 036 shows the boulder placement in the stream, but does not specify access to the stream. Will an access path be allowed within the LOD of the boulder placement at Station 201+50?	Yes, and a suggested access path for this area is depicted on the E&S-C plans, sheet 052 of 243.
54	Special Provisions	Structure Backfill	Can DDOT provide an assumption for the amount of Natural Channel Backfill that will be necessary to wash in all structures once all Salvaged Streambed Material has been exhausted? Should this amount be covered under Special Provision 54 Structure Backfill	The cost of Natural Channel Backfill is considered incidental to the cost of each in-stream structure. In general, for Riffle Grade Controls and the Rock Cascade, you can assume a Natural Channel Backfill amount of 10 to 15% of the total structure volume. However, no cost adjustments will be made if the volume of Natural Channel Backfill exceeds that amount.

157	Special Provisions	Step Pool	<p>The Step Pool Design calls out a design where the elevations of the large stones and small stones will vary. Can DDOT provide some clarification on the variances allowed in elevations?</p> <p>Can DDOT provide some clarification into the use of clay plugs in channels where backfill is not called for? Putting these plugs into the native material and not areas composed of backfill does not make sense since it would not backup groundwater (which is what plugs do).</p>	<p>The center Keystone in each Step Pool structure can vary in elevation by +/- 0.1 ft. The Bank Anchor Stones shall be placed so that they have a top elevation within a range of 0.5 to 0.8 ft above the top elevation of the Keystone. The smaller stones between the Keystone and Bank Anchor Stones can vary in elevation up to 0.5 ft in order to accommodate the siltling and interlocking described in the Step Pool Structure special provision.</p>
156	Special Provisions	Clay Channel Block	<p>Can DDOT provide some clarification into the use of clay plugs in channels where backfill is not called for? Putting these plugs into the native material and not areas composed of backfill does not make sense since it would not backup groundwater (which is what plugs do).</p>	<p>The clay channel blocks are included to back up any subsurface flow and encourage streamflow to stay on the surface of the streambed in a segment of the channel that goes dry in the summer time. The construction of the clay channel blocks is specified according to clay core trench construction standards used for ponds. A special backfill is not necessary.</p>
Item 220	Bid Forms & Drawings	Virginia Blueballs	Item 220 has 300 Virginia Blueballs-plans show 425	This has been addressed in Addendum 1.
Item 390	Bid Forms & Drawings	Chokeberry	Item 390 has 59 Chokeberry-plans show 62	This has been addressed in Addendum 1.
Item 410	Bid Forms & Drawings	Inkberry	Item 410 has 50 Inkberry - plans show 35	This has been addressed in Addendum 1.
Item 440	Bid Forms & Drawings	St. Johns Wort	Item 440 has 2000 St. Johns Wort - plans have 2600.	This has been addressed in Addendum 1.