AMENDMENT OF SOLICITATION / MODIFICATION OF CONTRACT	1. Contract Number DCKA-2015-B-0062	Page of Pages 1 | 2

2. Amendment/Modification Number	3. Effective Date	4. Requisition/Purchase Request No.	5. Solicitation Caption
Amendment No. 5 (A05)	DEC - 9 2015		Oxon Run Trail Rehabilitation Project

6. Issued by: Code
District Department of Transportation
Office of Contracting and Procurement
55 M Street SE, 7th Floor
Washington, DC 20003

7. Administered by (If other than line 6)

8. Name and Address of Contractor (No. street, city, county, state and zip code)

Code Facility

X 9A. Amendment of Solicitation No. DCKA-2014-B-0062

9B. Dated (5ee Item 11) October 21, 2015

10A. Modification of Contractor/Order No.

10B. Dated (See Item 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning _1_ copies of the amendment: (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) BY separate letter or fax which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such may be made by letter or fax, provided each letter or telegram makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. Accounting and Appropriation Data (If Required):

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTORS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14

	A. This change order is issued pursuant to (Specify Authority): 27 DCMR Chapter 3603 The changes set forth in Item 14 are made in the contract/order no. in item 10A.
	B. The above numbered contract/order is modified to reflect the administrative changes (such as changes in paying office, appropriation data etc.) set forth in item 14, pursuant to the authority of 27 DCMR, Chapter 36, Section 3601.2.
	C. This supplemental agreement is entered into pursuant to authority of:
	D. Other (Specify type of modification and authority) 27 DCMR 2008 Exercise of an Option

E. IMPORTANT: Contractor ☐ is not ☒ is required to sign this document and return _1_ copy to the issuing office.

14. Description of Amendment/Modification (Organized by UCF Section headings, including solicitation/contract subject matter where feasible.)

Invitation No.: DCKA-2015-B-0062 is an administrative change as follows:

A. Amendment No.4 posted on 12/4/2015 is renumbered to Amendment No. 5.

B. Delete page 12R and Replace with page 12RR.

Except as provided herein, all terms and conditions of the document referenced in item (9A or 10A) remain unchanged and in full force and effect.

15A. Name and Title of Signer (Type or print)		16A. Name of Contracting Officer: Courtney B. Lattimore Deputy Chief Contracting Officer	
15B. Name of Contractor (Signature)	15C. Date Signed	16B. District of Columbia (Signature of Contracting Officer)	16C. Date Signed 12/8/15

of the proposed work, wherever located. The inspection shall include notes, measurements, and a video cassette tape (VHS format) or DVD recording, or any other approved method by the COTR, with audio soundtrack, of all facilities. The audio DESCRIPTION of the inspection shall include the date, time, weather conditions, address/stationing/location, brief DESCRIPTION of the facility with contract name and number, and DESCRIPTION of physical conditions encountered.

Digital photos will be required on certain aspect for this process. Where the Contractor anticipates potential problems to impede the work progress, Note: If the Contractor does not have a record of these problems and a problem arises later, the Contractor will be held responsible for the necessary repairs (leaning/broken walls, leaks, running water, damage to driveway, concrete leads, etc.).
Two copies of all notes, measurements, video/DVD recordings, reports and data shall be submitted to the COTR, accompanied by a completed Department of Transportation standard transmittal from, as soon as these records are complete. Progress payments will not be made until this requirement is met. With the initial payment the contractor shall submit two (2) copies of the video(s)/DVD(s) for all locations under this contract that shows existing conditions prior to commencement of work.

The copies shall include phases of construction until the project is completed. No additional compensation over and above the reflected in the Schedule of Prices will be allowed for complying with this provision.

24. COMMON EXCAVATION, Item 202 002

This S.P. supplements Section 202 of the Standard Specifications.

1. GENERAL

Supplementing 202.01 and 202.02, work under this item shall include removal and disposal of existing asphalt trail as shown in the plans and as directed by the COTR.. Also included is special or hand excavation, if necessary, over, around, and under supports for existing or new utility lines and appurtenances uncovered from such base undercutting. Included as a part of this item is the demolition and disposal of the asphalt pavement and any concrete items existing and required to be removed for the construction of the trails, sidewalks and other items included in the contract.

When the excavation is near the root of a tree, the contractor must request the presence of a UFA officer at the site to give advice. Contractor must adhere to tree and root protection measures in Sections 207.03, 608.07 and 608.08.

The contractor shall notify PEPCO, two working days in advance of excavating in the vicinity of any high voltage cables. Notify Mr. Kenny Payne on (202) 388-2137 or at khpayne@pepco.com

Work under this item also includes "Hard Surface Pavement Excavation". Refer to section 202.03 of the standard specifications.

2. PAYMENT

Payment for COMMON EXCAVATION will also include costs for special or hand excavation, support for existing or new utility lines and appurtenances uncovered during excavation, and all tools, materials, equipment and incidentals necessary to complete the work as specified and as directed by the COTR.