AMENDMENT OF SOLICITATION / MODIFICATION OF CONTRACT	1. Contract Number DCRL-2017-T-0025	Page of Pages 1	2, plus attachments

2. Amendment/Modification Number	3. Effective Date	4. Requisition/Purchase Request No.	5. Solicitation Caption
A004	See Box 16C		**Audio Visual and Video Teleconferencing System for Office of Youth Empowerment**

6. Issued by: Code	7. Administered by (If other than line 6)
District of Columbia Child and Family Services Agency Contracts and Procurement Administration 200 I (Eye) Street SE Suite 2031 Washington, DC 20003	District of Columbia Child and Family Services Agency Office of the Deputy Director for Administration Administrative Operations 200 I (Eye) Street, SE Washington, DC 20003

8. Name and Address of Contractor (No. street, city, county, state and zip code)	9A. Amendment of Solicitation No. A002
	9B. Dated (See Item 11) 11/16/2016
	10A. Modification of Contract/Order No.
Facility	10B. Dated (See Item 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in item 14. The hour and date specified for receipt of Offers ☒ is extended. ☐ is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning 1 copies of the amendment: (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) BY separate letter or fax which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such may be made by letter or fax, provided each letter or telegram makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. Accounting and Appropriation Data (If Required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACT/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14

	A. This change order is issued pursuant to (Specify Authority): 27 DCMR, Chapter 36, Contract Modifications The changes set forth in Item 14 are made in the contract/order no. in item 10A.
	B. The above numbered contract/order is modified to reflect the administrative changes (such as changes in paying office, appropriation data etc.) set forth in item 14, pursuant to the authority of 27 DCMR, Chapter 36, Section 3601.2.
	C. This supplemental agreement is entered into pursuant to authority of:
	D. Other (Specify type of modification and authority) :27 DCMR 3601.2 (c): Unilateral Modification

E. IMPORTANT: Contractor ☒ is not ☐ is required to sign this document and return __ copies to the issuing office.

14. Description of Amendment/Modification (Organized by UCF Section headings, including solicitation/contract subject matter where feasible.)

1. The closing date for this solicitation has been extended to Monday, December 5, 2016 at 2:00pm.
2. Page one of the solicitation is revised. (See attached revised solicitation)
3. Attachment B Price schedule, page one revised. (See Attached revised solicitation)

(continued on page two)

15A. Name and Title of Signer (Type or print)		16A. Name of Contracting Officer **Tara Sigamoni**	
15B. Name of Contractor (Signature of person authorized to sign)	15C. Date Signed	16B. District of Columbia (Signature of Contracting Officer)	16C. Date Signed 12/01/2016

4. The cutoff for all requests for information/clarification is effective the date of this amendment.

5. Responses to the Requests for Information are as follows:

   Question 1: Will CFSA provide as built room design drawing before or after the an awardee has been awarded?

   Response 1: The room design drawings will be available to the awardee.

   Question 2: While the specification list CODEC it does not mention a specific manufacturer or specification for the CODEC, are we to assume that these are additional CISCO SX80 codecs totally 6 Codecs? If the other generally marked codecs are expected to be a different manufacturer and specification please specify?

   Response 2: (TelePresence) Cisco SX80 Codec, Precision 60 Cam, Touch 10. Codecs are not expected to be different.

   Question 3 Is there a loaded rate sheet template that will be provided or do we submit a rate sheet based on what positions we believe are needed to complete the project?

   Response 3: All vendors shall submit fully loaded rates for all contract line items.

GOVERNMENT OF THE DISTRICT OF COLUMBIA
Child and Family Service Agency

REQUEST FOR TASK ORDER BID

(REVISED 12/01/2016)

Solicitation No.: **DCRL-2017-T-0025**

Caption: **Audio Visual and Video Teleconferencing System for Office of Youth Empowerment**

Issuance Date: **Wednesday, November 16, 2016**

Due Date: ~~**Monday, November 28, 2016**~~ ~~**Friday, *December 2, 2016***~~ **Monday, December 5, 2016, no later than 2:00pm**

The District of Columbia Child and Family Services Agency, on behalf of the Office of Youth Empowerment has a need for the purchase and installation of Audio Visual and Teleconferencing Equipment for the new offices of the Office of Youth Empowerment.

The task order bid should be prepared according to the instructions listed below:

1. Bid Submission Requirements

The task order bid shall be submitted as "Task Order Bid in response to Solicitation No. DCKA-2017-T-0025"

The Bidder's Bid shall, at minimum, include:

a. A Bid in accordance with Attachment A;

b. Copy of the Bidder's DC Supply Price Schedule

c. Completed Price Schedule (Attachment B) – Revised ~~11/23/2016~~ **12/01/2016**

2. Task of Solicitation

Bid should be submitted online via email to lisa.minor-smith@dc.gov

MANDATORY SITE VISIT: It shall be **MANDATORY** that each bidder representative be present for a pre-bid site visit on Friday, November 18, 2016 or Tuesday, November 29, 2016. Please note: you are not required to attend both site visits. Attendees are to meet promptly at 10:00am at 3350 9th Street, NE, Washington, DC 20017. All attendees must sign in at this time. The purpose of this visit is for all prospective bidders to acquaint themselves with the conditions and requirements of the task to be performed. Attendees will be apprised of all conditions of installation and should take any necessary measurements. Bidders shall stay for the duration of the site visit. No allowances will be made for unreported conditions which a prudent bidder would recognize as affecting the work called for or implied by this bid. FAILURE TO COMPLY WITH THIS REQUIREMENT WILL RESULT IN REJECTION OF YOUR BID.

3. Bid Submission Date

The closing date for receipt of bids is no later than 2:00 P.M., ~~Monday, November 28, 2016.~~ ~~***Friday, December 2, 2016***~~, **Monday, December 5, 2016**

4. Evaluation for Award

(a) In order to be considered responsive, bidder must meet the following minimum requirements.

1) The bidder must propose goods/services which comply with their identified DC Supply Schedule

2) Must provide completed attachment B.

3) Submit all loaded rates in accordance with **Wage Determination 2015-4281, Revision 3, dated 4/8/16 available at www.wdol.gov**

5. Term of Contract

The period of performance shall be for one year from the date of award.

6. Attachments

Attachment A – Statement of Work
Attachment B – Price Schedule – Revised ~~11/23/2016~~ **12/01/2016**

ATTACHMENT A

GOVERNMENT OF THE DISTRICT OF COLUMBIA
CHILD AND FAMILY SERVICES AGENCY
OFFICE OF YOUTH EMPOWERMENT (OYE)

AUDIO VISUAL HD VIDEO TELECONFERENCE (VTC)

1. SCOPE OF SERVICES

The DC Child and Family Services Agency (DCCFSA), on behalf of the OYE needs the services of a contractor to design, provide, implement and fully integrate a state of the art Audio Visual HD Video Teleconference (VTC) system for the new offices of OYE, located at 3350 Ninth Street, NE, Washington, DC 20017. The Contractor must provide a turnkey solution that is fully calibrated and tested. The system must be able to support multipurposes, multi-party conferencing and personal computer (PC) presentations. The system must have the capability to facilitate Voice Over Internet Protocol (VoIP) conference audio calls utilizing codec and a touch-panel to provide full control of the AV system's functionality. The scope will also include the installation of iPads with secure enclosures to be recessed in-wall (must have dedicated power source POE); installation of wall-mount display monitors, mini PCs, to be mounted securely with brackets behind monitors or in centralized location; ceiling mounted HD projectors (minimum 6000 lumens of brightness); motorized retractable projection screens, HD cameras, microphones - (ceiling, wireless with charging base, and lapel); and installation of AV wall interface plates to integrate network connections (laptop, VGA with audio, HDMI, data).

2. REQUIREMENTS

The contractor will perform the following services:

2nd Floor - Hall way (waiting area)

- Install wall mount display monitor *42''minimum*, a mini pc, AV input interface wall plate - (VGA w/audio, HDMI, data, power outlet).

2nd Floor Conference Room – 200-04 (VTC)

- Install *flat panel HD display monitor70'' minimum/80' maximum.*
- Integrate custom wireless control system touch panel that will be recessed in-wall (close proximity to podium location and display screen).
- Install ceiling microphones (2), ceiling speakers (4), one front facing HD camera, (1) rare facing HD camera (minimum 1080 pixel video 12 pan tilt zoom, (PTZ).
- Install AV input plates (VGA with audio, HDMI), located at front side wall.
- **Install 1 iPad (9.45x6.67x0.03 inches) secure enclosures that will be recessed in-wall outside of room entrance with dedicated power source.**
- Install dedicated standing rack mount to house backend AV equipment (centralized location), 2x2 ceiling mount AV rack enclosure with necessary cooling and ventilation requirement.

- VTC system must be compatible with WebEx applications and other similar third party video conferencing applications.

2nd Floor - Training Room 200-13

- Install ceiling mounted HD projector and motorized (w/remote) wall mount retractable projection screen 106'' diagonal minimum, ceiling speakers (2), AV wall interface plates (VGA w/audio, HDMI, data, electrical), located at front side wall. Install 2x2 ceiling mount AV rack enclosure with necessary cooling and ventilation requirement.
- *Install 1 iPad (9.45x6.67x0.03 inches) secure enclosures that will be recessed in-wall outside of room entrance with dedicated power source. (CFSA will provide iPads)*

2nd Floor - Staff Room 200-12

- Install wall mount display monitor *46'' minimum*; install mini pc, AV input interface wall plate - (VGA w/audio, HDMI, data, power outlet).

3rd Floor - Conference Room 300-04

- Install *flat panel interactive touch display monitor 70'' minimum*, AV input interface wall plates - (VGA w/audio, HDMI, data, power outlet, USB charger), 1 located at front side wall and one in floor box located toward the center of the room. Ceiling speakers (4) 6'', ceiling microphones (2).
- Integrate custom wireless control system touch panel recessed in-wall (close proximity to podium location.
- *Install 1 iPad (9.45x6.67x0.03 inches) secure enclosures that will be recessed in-wall outside of room entrance with dedicated power source. (CFSA will provide iPads)*

3rd Floor - Parent Conference Room 300-05

- *Install 1 iPad (9.45x6.67x0.03 inches) secure enclosures that will be recessed in-wall outside of room entrance with dedicated power source. (CFSA will provide iPads)*

3rd Floor - Conference Room 300-20

- *Install 1 iPad (9.45x6.67x0.03 inches) secure enclosures that will be recessed in-wall outside of room entrance with dedicated power source. (CFSA will provide iPads)*

3rd Floor - Teen Rec Room 300-09

- Install wall mount display monitor 46''minimum; install mini pc, AV input interface wall plate - (VGA w/audio, HDMI, data, power outlet).

3rd Floor - Training Room 300-10

- Install ceiling mount HD projector, wall mount motorized retractable projection screen 106 inch diagonal minimum, ceiling speakers (2), AV wall interface plates (VGA w/audio, HDMI, data, power outlets.

- Install 1 iPad (9.45x6.67x0.03 inches) secure enclosures that will be recessed in-wall outside of room entrance with dedicated power source. *(CFSA will provide iPads)*

(IT-Room) – 3RD Floor

IT room must be designed as centralized location for managing peripherals and must be scalable to add services as needed. Contractor shall install all necessary backend equipment, provide all mounting hardware, all UPS power distribution units (20 amp minimum) or accordance to equipment requirements.

- Gangable AV hardware rack with appropriate shelving and thermal management, to include rack mountable 123W or (***recommended***) DC power distribution unit.
- Contractor shall provide rack mountable switches with POE feature (***48 port minimum***) all necessary Uni stacking cables, as well as all necessary licenses.
- Install (decoders, encoders transmitters, scalers, routing device modules, all mounting hardware and cables- HDMI and fiber ports.
- LED commercial display 26" minimum, dual swing arm wall display mount 18" minimum extension.
- Wireless (keyboard) computing RF-512 or similar.

3. CONTRACTOR'S RESPONSIBILITY

3.1 The contractor shall provide all equipment except where specified:

3.2 Display Monitors shall be of commercial grade to prevent screen burnout

3.3 Provide CFSA personnel with training to utilize the new equipment

ATTACHMENT B - PRICE SCHEDULE (REVISED 12/01/2016)

The District contemplates award of a firm-fixed price contract for the services to be performed at the unit prices specified herein in Section B.1. **All vendors shall submit fully loaded rates for contract line items.**

2nd Floor – Hallway (waiting area)

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price Per Unit	Estimated Total Amount
0001-A	Wall Mount Monitor, 42" minimum	1	ea	$ _____	$ _____
0002-A	Medium Fusion micro-adjustable tilt wall mount	1	ea	$ _____	$ _____
0003-A	Metal Stud Anchor Kit	3	ea	$ _____	$ _____
0004-A	ASUS VivioMini UN45 mini PC (*OS windows 10 pro, CPU - Intel 6th generation Core i5-Processor, Storage 256GB SSD, Memory 8GB*) with wireless keyboard and mouse	1	ea	$ _____	$ _____
0005-A	AV Input Interface wall plate (VGA w/ audio, HDMI, data, power outlets)	1	ea	$ _____	$ _____
	TOTAL FOR CLINS 0001-A THRU 0005-A)				

2nd Floor – Conference Room 200-04 (VTC)

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price per Unit	Estimated Total Amount
0001-B	Flat Panel HD Display Monitor, 80" maximum	1	ea	$ _____	$ _____
0002-B	Large Fusion micro-adjustable tilt wall mount	1	ea	$ _____	$ _____
0003-B	Metal Stud Anchor Kit	3	ea	$ _____	$ _____
0004-B	CISCO SX80 Codec, Precision 60 CAM, Touch 10 – brand name or equal	1	ea	$ _____	$ _____

0005-B	License- SW Encryption Module	1	ea	$ _____	$ _____
0006-B	License – Multi-Site Software Option	1	ea	$ _____	$ _____
0007-B	Codec	1	ea	$ _____	$ _____
0008-B	Rack Ears	1	ea	$ _____	$ _____
0009-B	Camera – TelePresence Precision 60 Camera- Auto Expand Only	1	ea	$ _____	$ _____
0010-B	Touch 10-Auto Expand Only	1	ea	$ _____	$ _____
0011-B	POE Injector	1	ea	$ _____	$ _____
0012-B	Power Supply – 12VDC – 40W	2	ea	$ _____	$ _____
0013-B	Cable – Power-US, Black 1.8m	4	ea	$ _____	$ _____
0014-B	Cable – DVI to VGA, Phoenix Audio Connector	1	ea	$ _____	$ _____
0015-B	Cable- Ethernet – Grey 12.5m	1	ea	$ _____	$ _____
0016-B	Cable –Ethernet- Grey 4m	1	ea	$ _____	$ _____
0017-B	Camera-TelePresence Precision 60 Camera	1	ea	$ _____	$ _____
0018-B	Multiple Output Power Supply Thin profile wall mount bracket for Precision 60 Camera	1	ea	$ _____	$ _____
0019-B	7" Touch Screen Controller – Black	1	ea	$ _____	$ _____
0020-B	Table Top Kit for TWS 752-Black	1	ea	$ _____	$ _____
0021-B	Encoder with HDMI/VGA and fiber port	1	ea	$ _____	$ _____
0022-B	Decoder with HDMI and fiber port	1	ea	$ _____	$ _____

0023-B	Audio transceiver with L/R input, L/R output and 2 contact ports	1	ea	$ _____	$ _____
0024-B	Mounting wings for N series devices	4	ea	$ _____	$ _____
0025-B	Audio Processor with Telephone Conferencing	1	ea	$ _____	$ _____
0026-B	Expander Module – 4-in	2	ea	$ _____	$ _____
0027-B	Low Profile Boundary Microphone Cardioid (Black)	2	ea	$ _____	$ _____
0028-B	Low Profile Boundary Microphone – Bidirectional (Black)	6	ea	$ _____	$ _____
0029-B	iPad Flush Mount with Black Box and Cover-Box	1	ea	$ _____	$ _____
0030-B	POE to USB Charger Universal USB Charger	1	ea	$ _____	$ _____
0031-B	2 x 2 ceiling mount A/V Rack Enclosure	1	ea	$_____	$_____
0032-B	Ceiling Speakers	4	ea	$_____	$_____
	TOTAL FOR CLINS 0001-B THRU 0032-B				

2nd Floor – Training Room 200-13

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price Per Unit	Estimated Total Amount
0001-C	Ceiling mounted HD projector	1	ea	$ _____	$ _____
0002-C	Motorized (w/ remote) wall mount retractable projection screen 106" minimum	1	ea	$ _____	$ _____
0003-C	Ceiling speakers	2	ea	$ _____	$ _____
0004-C	AV wall interface plates (VGA w/ audio, HDMI, data, electrical)	1	ea	$ _____	$ _____
0005-C	2 x 2 ceiling mount AV rack enclosure with necessary cooling and ventilation requirement	1	ea	$ _____	$ _____
0006-C	Codec	1	ea	$ _____	$ _____

0007-C	Rack Ears	1	ea	$ _____	$ _____
0008-C	Camera – TelePresence Precision 60 Camera- Auto Expand Only	1	ea	$ _____	$ _____
0009-C	Touch 10-Auto Expand Only	1	ea	$ _____	$ _____
0010-C	POE Injector	1	ea	$ _____	$ _____
0011-C	Power Supply – 12VDC – 40W	2	ea	$ _____	$ _____
0012-C	Cable – Power-US, Black 1.8m	4	ea	$ _____	$ _____
	TOTAL FOR CLINS 0001-C THRU 0012-C				

2nd Floor – Staff Room 200-12

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price Per Unit	Estimated Total Amount
0001-D	Wall Mount Display monitor, 46" minimum	1	ea	$ _____	$ _____
0002-D	ASUS VivoMini UN45 mini PC (*OS windows 10 pro, CPU - Intel 6th generation Core i5-Processor, Storage 256GB SSD, Memory 8GB*)	1	ea	$ _____	$ _____
0003-D	A/V Wall Interface plates (VGA w/ audio, HDMI, Data, power outlet)	1	ea	$_____	$_____
	TOTAL FOR CLIN 0001-D THRU 0003-D				

3rd Floor Conference Room – 300-04

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price per Unit	Estimated Total Amount
0001-E	Flat Panel HD Display Monitor, 70" maximum	1	ea	$ _____	$ _____
0002-E	Large Fusion micro-adjustable tilt wall mount	1	ea	$ _____	$ _____

0003-E	Metal Stud Anchor Kit	3	ea	$ _____	$ _____
0004-E	CISCO SX80 Codec, Precision 60 CAM, Touch 10 – brand name or equal	1	ea	$ _____	$ _____
0005-E	License- SW Encryption Module	1	ea	$ _____	$ _____
0006-E	License – Multi-Site Software Option	1	ea	$ _____	$ _____
0007-E	Cisco SX 80 Codec, Precision 60 Cam, Touch 10	1	ea	$ _____	$ _____
0008-E	Rack Ears	1	ea	$ _____	$ _____
0009-E	Camera – TelePresence Precision 60 Camera- Auto Expand Only	1	ea	$ _____	$ _____
0010-E	Touch 10-Auto Expand Only	1	ea	$ _____	$ _____
0011-E	POE Injector	1	ea	$ _____	$ _____
0012-E	Power Supply – 12VDC – 40W	2	ea	$ _____	$ _____
0013-E	Cable – Power-US, Black 1.8m	4	ea	$ _____	$ _____
0014-E	Cable – DVI to VGA, Phoenix Audio Connector	1	ea	$ _____	$ _____
0015-E	Cable- Ethernet – Grey 12.5m	1	ea	$ _____	$ _____
0016-E	Cable –Ethernet- Grey 4m	1	ea	$ _____	$ _____
0017-E	Camera-TelePresence Precision 60 Camera	1	ea	$ _____	$ _____
0018-E	Multiple Output Power Supply Thin profile wall mount bracket for Precision 60 Camera	1	ea	$ _____	$ _____
0019-E	7" Touch Screen Controller – Black	1	ea	$ _____	$ _____
0020-E	Table Top Kit for TWS 752-Black	1	ea	$ _____	$ _____

0021-E	Encoder with HDMI/VGA and fiber port	1	ea	$ _____	$ _____
0022-E	Decoder with HDMI and fiber port	1	ea	$ _____	$ _____
0023-E	Audio transceiver with L/R input, L/R output and 2 contact ports	1	ea	$ _____	$ _____
0024-E	Mounting wings for N Series Devices	4	ea	$_____	$_____
0025-E	E-Audio Processor with Telephone Conferencing	1	ea	$ _____	$ _____
0026-E	Expander Module – 4-in	2	ea	$ _____	$ _____
0027-E	Low Profile Boundary Microphone Cardioid (Black)	2	ea	$ _____	$ _____
0028-E	Low Profile Boundary Microphone – Bidirectional (Black)	6	ea	$ _____	$ _____
0029-E	iPad Flush Mount with Black Box and Cover-Box	1	ea	$ _____	$ _____
0030-E	POE to USB Charger Universal USB Charger	1	ea	$ _____	$ _____
	TOTAL FOR CLINS 0001-E THRU 0030-E				

3rd Floor Parent Conference Room 300-05

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price Per Unit	Estimated Total Amount
0001-F	iPad Flush Mount with Black Box and Cover-Box	1	ea	$_____	$_____
	TOTAL FOR CLIN 0001-F				

3rd Floor Conference Room 300-20

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price Per Unit	Estimated Total Amount
0001-G	iPad Flush Mount with Black Box and Cover-Box	1	ea	$_____	$_____
	TOTAL FOR CLIN 0001-G				

3rd Floor Teen Recreation Room 300-09

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price Per Unit	Estimated Total Amount
0001-H	Wall Mount display monitor, 46" minimum	1	ea	$ _____	$ _____
0002-H	ASUS VivoMini UN45 mini PC(*OS windows 10 pro, CPU - Intel 6th generation Core i5-Processor, Storage 256GB SSD, Memory 8GB*)	1	ea	$ _____	$ _____
0003-H	A/V Wall Interface plates (VGA w/ audio, HDMI, Data, power outlet)	1	ea	$_____	$_____
	TOTAL FOR CLINS 0001-H THRU 0003-H				

3rd Floor – Training Room 300-10

Contract Line Item Number (CLIN)	Description	Estimated Quantity	Unit	Price Per Unit	Estimated Total Amount
0001-I	Ceiling mounted HD projector	1	ea	$ _____	$ _____
0002-I	Motorized (w/ remote) wall mount retractable projection screen 106" minimum	1	ea	$ _____	$ _____
0003-I	Ceiling speakers	2	ea	$ _____	$ _____
0004-I	AV wall interface plates (VGA w/ audio, HDMI, data, electrical)	1	ea	$ _____	$ _____
0005-I	2 x 2 ceiling mount AV rack enclosure with necessary cooling and ventilation requirement	1	ea	$ _____	$ _____
0006-I	Cisco SX 80 Codec, Precision 60 Cam, Touch 10	1	ea	$ _____	$ _____
0007-I	Rack Ears	1	ea	$ _____	$ _____

0008-I	Camera – TelePresence Precision 60 Camera- Auto Expand Only *brand name or equal*	1	ea	$ _____	$ _____
0009-I	Touch 10-Auto Expand Only	1	ea	$ _____	$ _____
0010-I	POE Injector	1	ea	$ _____	$ _____
0011-I	Power Supply – 12VDC – 40W	2	ea	$ _____	$ _____
0012-I	Cable – Power-US, Black 1.8m	4	ea	$ _____	$ _____
	TOTAL FOR CLINS 0001-I THRU 0012-I				

3rd Floor IT Room

Contract Line Item No. (CLIN)	Description	Estimated Quantity	Unit	Price Per Unit	Estimated Total Amount
0001-J	48 port rack mount gigabit switch with POE and 10G stacking SFP Port	2	ea	$ _____	$ _____
0002-J	Stack/Unistack Stacking Cable 0.5m	2	ea	$ _____	$ _____
0003-J	Licensing	2	ea	$_____	$_____
0004-J	AVB License	2	ea	$_____	$_____
0005-J	3 Series Control System	1	ea	$_____	$_____
0006-J	N-Series Controller	1	ea	$_____	$_____
0007-J	16 channel 12v power supply	1	ea	$_____	$_____
0008-J	Mounting wings for N series devices	4	ea	$_____	$_____
0008-J	1RU shelf for two N series devices side by side	12	ea	$_____	$_____

0009-J	Encoder with HDMI/VGA and fiber port	2	ea	$_____	$_____
0010-J	Decoder with HDMI and fiber port	1	ea	$_____	$_____
0011-J	USB over Ethernet with Routing – Device Module	1	ea	$_____	$_____
0012-J	Wireless Computing	1	ea	$_____	$_____
0013-J	LED DM Series Commercial Display – 32" Class Medium Thinstall Dual Swing Arm Wall brand name or equal	1	ea	$_____	$_____
0014-J	Display Mount – 18" Extension	1	ea	$_____	$_____
0015-J	Metal Stud Anchor Kit	3	ea	$_____	$_____
0016-J	Rackmount 20 amp UPS with IP control – brand name or equal	3	ea	$_____	$_____
0017-J	Rackmount 20 amp power distribution unit with Series Protection	1	ea	$_____	$_____
0018_J	Rackmount 20 amp power distribution unit	1	ea	$_____	$_____
0019-J	Series Gangable AV Rack	2	ea	$_____	$_____
0020-J	Rack shelves, power and thermal management	1	ea	$_____	$_____
0021-J	Wire, connectors and installation accessories		ea	$_____	$_____
	TOTAL FOR CLINS 0001-J THRU 0021-J				
	TOTAL BID PRICE FOR ALL CLINS				