

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. Contract Number POKA-2003-B-0064-VH		Page of Pages 1 31	
2. Amendment/Modification Number 3		3. Effective Date 9/15/2004		4. Requisition/Purchase Request No.		5. Solicitation Caption Reconstruction of Southern Ave., SE	
6. Issued By: District Department of Transportation Construction Contract Branch 2000 14th Street, NW, 6th Floor Washington, DC 20009				7. Administered By (If other than line 6) Procurement Support Branch 2000 14th Street, NW, 3rd Floor, Bid Room Washington, DC 20009			
8. Name and Address of Contractor (No. Street, city, country, state and ZIP Code)				(X)		9A. Amendment of Solicitation No. POKA-2003-B-0064-VH	
						9B. Dated (See Item 11) 8/5/2004	
						10A. Modification of Contract/Order No.	
						10B. Dated (See Item 13)	
Code		Facility					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
X The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input checked="" type="checkbox"/> is extended. <input type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment: (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or fax which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or fax, provided each letter or telegram makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. Accounting and Appropriation Data (If Required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14							
A. This change order is issued pursuant to: (Specify Authority)							
The changes set forth in Item 14 are made in the contract/order no. in item 10A.							
B. The above numbered contract/order is modified to reflect the administrative changes (such as changes in paying office, appropriation date, etc.) set forth in item 14, pursuant to the authority of 27 DCMR, Chapter 36, Section 3601.2.							
C. This supplemental agreement is entered into pursuant to authority of:							
D. Other (Specify type of modification and authority)							
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input checked="" type="checkbox"/> is required to sign this document and return <u>1</u> copies to the issuing office.							
14. Description of amendment/modification (Organized by UCF Section headings, including solicitation/contract subject matter where feasible.)							
Addendum No. 3 - is necessary to changed the Bid Opening Date and to answer questions raised at the Pre-Bid Meeting.							
Except as provided herein, all terms and conditions of the document referenced in Item (9A or 10A) remain unchanged and in full force and effect							
15A. Name and Title of Signer (Type or print)				16A. Name of Contracting Officer Jerry M. Carter			
15B. Name of Contractor		15C. Date Signed		16B. District of Columbia		16C. Date Signed 9/15/2004	
(Signature of person authorized to sign)				(Signature of Contracting Officer)			

Government of the District of Columbia
District Department of Transportation
Construction Contract Branch
2000 - 14th Street, N.W. 6th Floor
Washington, D.C. 20009

ADDENDUM NO. 3 **ISSUED** **September 15, 2004** **Page(s)**
POKA-2003-B-0064-VH

**RECONSTRUCTION OF SOUTHERN AVENUE, S.E. FROM
PENNSYLVANIA AVENUE TO SUITLAND ROAD**

F.A.P. NO.: STP-3307 (10)

BIDDERS shall acknowledge receipt of this addendum on official Bid Form. Failure to do so may result in rejection of your bid.

CURRENT BID OPENING DATE: September 21, 2004

BIDDERS are informed that the above named project is modified as follows:

BID OPENING DATE

The Bid Opening Date has been extended from September 21, 2004 to September 24, 2004.

SPECIFICATIONS

On page 49, add SP. No. **49. - TIMBER GROUND MOUNT SIGN POSTS 4"X4" Item No. 620 002** to read as follow:

ADD the following sentence to Section 620.01 (D) (DWG. No. 620.01)
"Payment will also include class F concrete footing."

ADD: DCDPW Standard Drawing No. 620.01 - Permanent Break-Away Wood Sign Post Small Signs (1 page) to **DCDPW STANDARD DETAILS (Attached with the Addendum)**.

ADDENDUM NO. 3
Reconstruction of Southern Avenue
from Pennsylvania Avenue to Suitland Road

APPENDIX D: Add the CCTV RG-6/U Type camera specifications (4 pages) (**Attached with the Addendum**).

WAGE RATES

DELETE: General Wage Decision No. DC030001, Modification No. 0, dated 6/13/03 and Replace with General Wage Decision No. DC030001, Modification No. 14, dated 8/20/04.

BID FORMS AND PROPOSAL

DELETE: the Pay Item Schedule in its entirety and replace with the **REVISED** Pay Item Schedule pages **1R-8R**.

PLANS

DELETE: sheet number 10 of 49 and **REPLACE** with the **REVISED** sheet **10R of 49**.

DELETE: sheet TS1 and TS3 and **REPLACE** with the **REVISED** sheet **TS1R** and **TS3R**.

Responses to prospective bidders' questions at the Pre-Bid meeting held on August 24, 2004 are given on Electrical Design as follows:

Question A1: Dwg TS-11 shows a 6W, 4" C Ductbank from Manhole M2B to existing Pullback near Manhole M3B. Dwg. TS-4 shows this ductbank as existing.

Response A1: M2B is a proposed Manhole there is no existing conduit to it. The existing conduit to this pull box goes to an existing PEPCO manhole.

Question A2: Dwg TS-11 and TS-12 show a new (one 12 PR#19 AWG Communication Cable) Detector Cable in a PEPCO Duct from existing detector loops north of Davis Street to Pullbox and ductbank (Identified in Question A1) to TC-5. However, Dwg TS-13 identifies the loop wires as (four 1c#14 AWG Shld) for the four existing loops, What are the loop detector lead-in cables supposed to be?

Response A2: Lead in cable is 1c#14 AWG Shielded.

ADDENDUM NO. 3

**Reconstruction of Southern Avenue
from Pennsylvania Avenue to Suitland Road**

Question A3: DwgTS-11 & TS-12 show (1-12 PR#19 AWG and 1-25 PR#19 AWG Communication Cable) from TC-4 to TC-5, and a (1-25 PR#19 AWG Communications Cables) from TC-5 to TC-3. However, notes 1 & 2 on those drawings suggest that these Communications Cables should be 1-12 PR#19 AWG each. What is the design intention?

Response A3: Communications Cable from TC-4 to TC-5 is 25 pairs
Communications Cable from TC-5 to TC-3 is 25 pairs

Question: A4 Dwg TS-10 shows a Traffic Control Cabinet at the Southeast Corner of Pennsylvania Avenue and Alabama Avenue with a symbol calling for a new Loop Detector Lead-In. Where are the Detector Lead-In Cables to go?

Response A4: No loop lead in cable in this location.

ADDENDUM NO. 3
Reconstruction of Southern Avenue
from Pennsylvania Avenue to Suitland Road

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2003B0064VH

PROJECT(S): FAP NO. STP-3307(10)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PARTICIPATING TRAFFIC SIGNALIZATION WORK

0010	000511 Unassigned Special Item -LS - DC DPW LABOR COST FOR TRAFFIC SIGNAL WORK	LUMP	LUMP		4400.00	
0020	307010 Convert Fire Hydrant	4.000 EACH	.		.	
0030	313002 Abandon Basin Connecting Pipe CLEAN SEWER STRUCTURE	1.000 EACH	.		.	
0040	313008 Abandon Storm Inlet CLEAN PCC PIPE	600.000 EACH	.		.	
0050	618999 Payment to PEPCO for connection and disconnection of service to streetlights and traffic signals PAYMENT TO PEPCO FOR DISCON AND CON OF SVCE TO ST LIGHT AND TRAFFIC SIGNAL	LUMP	LUMP		7500.00	
0060	626002 Engineer's Field Facilities	LUMP	LUMP		.	
0070	626011 Progress Photographs	LUMP	LUMP		.	
0080	626015 As-Built Drawings	LUMP	LUMP		.	
0090	627002 Field Layout	LUMP	LUMP		.	

SCHEDULE OF ITEMS

CONTRACT ID: KA2003B0064VH

PROJECT(S): FAP NO. STP-3307(10)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
	SECTION 0001 TOTAL					.

SECTION 0002 PARTICIPATING ROADWAY WORK
ALT GROUP 01

0100	000003 Employee Training	1000.000				
		HR	.		.	
0110	201002 Clear and Grub	LUMP	LUMP			.
0120	202002 Common Excavation	2600.000				
		CY	.		.	
0130	204004 Borrow Embankment Fill	200.000				
		CY	.		.	
0140	209002 Aggregate Base Course	2500.000				
		CY	.		.	
0150	211991 Scarifying Special Item - SY - GEOTEXTILE FILTER FABRIC	6800.000				
		SY	.		.	
0160	305002 Ductile Iron Pipe, 4 - 8 Inch	20.000				
		LF	.		.	
0170	309002 Sewer Manhole on Sewer 48 Inch and Less Dia.	30.000				
		VLF	.		.	
0180	310006 Standard Triple Basin	4.000				
		EACH	.		.	

District Department of Transportation

PAGE:

3R

DATE:

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: KA2003B0064VH

PROJECT(S): FAP NO. STP-3307(10)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0190	310008 Basin Connect PCC Pipe, Class III, 15 Inch	120.000 LF	.		.	
0200	310020 Triple Type S Basin	1.000 EACH	.		.	
0210	311002 Adjust Sewer-Water-Utility Manhole Frame	22.000 EACH	.		.	
0220	311004 Reset Sewer-Water-Utility Manhole Frame	14.000 EACH	.		.	
0230	311016 Furnish Sewer-Water Manhole Frame	1.000 EACH	.		.	
0240	311026 Replace Existing Basin with Double Basin	4.000 EACH	.		.	
0250	311028 Replace Existing Basin with Triple Basin	8.000 EACH	.		.	
0260	403010 AC Surface, Class C	300.000 TON	.		.	
0270	406002 Tack Coat	3000.000 SY	.		.	
0280	411002 Temporary AC	50.000 TON	.		.	
0290	501008 Reinforced PCC Pavement, 10 Inch	6000.000 SY	.		.	

District Department of Transportation

PAGE:

4R

DATE:

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: KA2003B0064VH

PROJECT(S): FAP NO. STP-3307(10)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	501014 Extra Welded Wire Fabric, Style 66-46	100.000 SY	.		.	
0310	501022 Additional Standard Portland Cement	100.000 BAGS	.		.	
0320	501992 Portland Cement Concrete Pavement Special Item -SY - REINF. HIGH EARLY STRENGTH PAEVEMENT, 10 INCH	1500.000 SY	.		.	
0330	504006 PCC Driveway-Alley Entrance, 7 Inch 501	150.000 SY	.		.	
0340	505030 Anchor Bolts - Paving	50.000 EACH	.		.	
0350	602010 Standard PCC Coping	15.000 CY	.		.	
0360	607044 Safety Fence Shielding SAFETY FENCE SHIELDING	1200.000 LF	.		.	
0370	608004 PCC Sidewalk, 4 Inch	500.000 SY	.		.	
0380	608016 Repair-Replace PCC Sidewalk, 4 Inch	350.000 SY	.		.	
0390	609036 PCC Gutter	80.000 CY	.		.	

District Department of Transportation

PAGE:

5R

DATE:

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: KA2003B0064VH

PROJECT(S): FAP NO. STP-3307(10)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	609068 Furnish and Set 8"x12" Granite Straight Curb	2000.000 LF	.		.	
0410	609072 Furnish and Set 8"x12" Granite Circular Curb, Radius 10-100 Ft.	520.000 LF	.		.	
0420	609204 PCC Wheelchair/Bicycle Ramp	55.000 SY	.		.	
0430	610018 Sod with 3 Inch Topsoil	2000.000 SY	.		.	
0440	611212 Acer platanoides (Norway Maple) 3 - 3 1/2 Inch Cal., B&B	1.000 EACH	.		.	
0450	611811 Quercus acutissima (Sawtooth Oak) 2 1/2 - 3 Inch Cal., B&B	1.000 EACH	.		.	
0460	612002 Mobilization	LUMP	LUMP		.	
0470	614992 PCC Traffic Barriers Special Item - LF - PORTABLE PRECAST PCC BARRIERS WITH BARRIER MARKERS	1800.000 LF	.		.	
0480	616004 Construction Lane Closing	LUMP	LUMP		.	
0490	616006 Remove Lane Markings	1250.000 SF	.		.	

District Department of Transportation

PAGE:

6R

DATE:

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: KA2003B0064VH

PROJECT(S): FAP NO. STP-3307(10)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0500	616008 Temporary Construction Sign Supports	38.000 EACH	.		.	
0510	616012 Construction Warning and Detour Signs	6000.000 SF	.		.	
0520	616014 ReflectORIZED Traffic Cones	150.000 EACH	.		.	
0530	616016 Flashing Amber Warning Lights, Type "B"	32.000 EACH	.		.	
0540	616022 Construction Sign Warning Flags	32.000 EACH	.		.	
0550	616024 Type III PVC Barricade	8.000 EACH	.		.	
0560	616028 Traffic Drums	300.000 EACH	.		.	
0570	616054 Thermoplastic Pavement Arrow RETROREFLECTIVE PREFORMED PATTERNED CONTRAST LANE ARROWS	16.000 EACH	.		.	
0580	616090 Construction Zone Attenuator	6.000 EACH	.		.	
0590	616110 Portable Variable Message Sign	2.000 EACH	.		.	

District Department of Transportation

PAGE:

7R

DATE:

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: KA2003B0064VH

PROJECT(S): FAP NO. STP-3307(10)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0600	616992 Traffic Control Special Item - EACH - FLASHING ARROW PANEL - TYPE C	EACH 6.000	.		.	
0610	616994 Traffic Control Special Item - LF - RETROREFLECTETIVE PREFORMED PATTERNED CONTRAST LANE MARKING, 4'' DASH, W OR Y	LF 100.000	.		.	
0620	616994 Traffic Control Special Item - LF - RETROREFLECTIVE PREFORMED PATTERNED CONTRAST LANE MARKING, 4'', W OR Y	LF 3600.000	.		.	
0630	616994 Traffic Control Special Item - LF - RPPC LANE MARKING 12", WHITE	LF 350.000	.		.	
0640	616994 Traffic Control Special Item - LF - RPPC LANE MARKING 6'' , WHITE	LF 350.000	.		.	
0650	616994 Traffic Control Special Item - LF - RPPC LANE MARKING 8", WHITE	LF 20.000	.		.	
0660	618991 Electrical Work Special Item -LS- ELECTRICAL AND TRAFFIC SIGNAL WORK	LUMP	LUMP		.	
0670	620002 Timber Ground Mounted Sign Posts, 4x4 Inch	LF 160.000	.		.	

District Department of Transportation

PAGE:

8R

DATE:

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: KA2003B0064VH

PROJECT(S): FAP NO. STP-3307(10)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0680	620014 Traffic Sign Panels	100.000 SF	.		.	
0690	620040 Federal Aid Project Sign	2.000 EACH	.		.	
0700	620993 Traffic Signing Special Item - EACH - D. C. REBUILT SIGN	2.000 EACH	.		.	
0710	620993 Traffic Signing Special Item - EACH - REMOVE/REINSTALL EXISTING TRAFFIC SIGNS	40.000 EACH	.		.	
0720	621991 Pavement Profiling (Milling) Special Item - SY - PAVEMENT PROFILLING 2.5" (MILLING)	3000.000 SY	.		.	
0730	624002 Steel Protection Plate, 5x10 Ft.	10.000 EACH	.		.	
0740	628002 Erosion and Sediment Control	LUMP	LUMP		.	
	SECTION 0002 TOTAL				.	
	TOTAL BID				.	