

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. Contract Number POKA-2004-B-0018-JJ	Page of Pages 1 3	
2. Amendment/Modification Number 7		3. Effective Date 12/8/2004		4. Requisition/Purchase Request No.	
5. Solicitation Caption Reconstruction of F Street, NW					
6. Issued By: District Department of Transportation Construction Contract Branch 2000 14th Street, NW, 6th Floor Washington, DC 20009			7. Administered By (If other than line 6) Procurement Support Branch 2000 14th Street, NW, 3rd Floor, Bid Room Washington, DC 20009		
8. Name and Address of Contractor (No. Street, city, country, state and ZIP Code)			(X) 9A. Amendment of Solicitation No. POKA-2004-B-0018-JJ		
			9B. Dated (See Item 11) 9/28/2004		
			10A. Modification of Contract/Order No.		
			10B. Dated (See Item 13)		
Code		Facility			
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS					
X The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input type="checkbox"/> is extended. <input checked="" type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or fax which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or fax, provided each letter or telegram makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.					
12. Accounting and Appropriation Data (If Required)					
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14					
A. This change order is issued pursuant to: (Specify Authority)					
The changes set forth in Item 14 are made in the contract/order no. in item 10A.					
B. The above numbered contract/order is modified to reflect the administrative changes (such as changes in paying office, appropriation date, etc.) set forth in item 14, pursuant to the authority of 27 DCMR, Chapter 36, Section 3601.2.					
C. This supplemental agreement is entered into pursuant to authority of:					
D. Other (Specify type of modification and authority)					
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input checked="" type="checkbox"/> is required to sign this document and return <u>1</u> copies to the issuing office.					
14. Description of amendment/modification (Organized by UCF Section headings, including solicitation/contract subject matter where feasible.)					
<p>The Bid Opening of December 15, 2004 is not extended</p> <p>This addenda consists of this page and 2 pages attached hereto</p>					
Except as provided herein, all terms and conditions of the document referenced in Item (9A or 10A) remain unchanged and in full force and effect					
15A. Name and Title of Signer (Type or print)			16A. Name of Contracting Officer Jerry M. Carter		
15B. Name of Contractor		15C. Date Signed		16B. District of Columbia	
				16C. Date Signed 12/8/2004	
(Signature of person authorized to sign)			(Signature of Contracting Officer)		

Government of the District of Columbia
Department of Transportation
Construction Contract Branch
2000-14th Street, N.W. 6th Floor
Washington, D.C. 20009

ADDENDUM No. 7 ISSUED: December 8, 2004 2 pages

Invitation No. POKA-200-B-0018-JJ
Title: Reconstruction of F Street NW, from 17th to 23rd Street

BIDDERS shall acknowledge receipt of this addendum on official Bid Form. Failure to do so may result in rejection of your bid.

CURRENT BID OPENING

December 15th, 2004

BIDDERS are informed that the above named project is modified as follows:

SPECIFICATIONS & BID FORMS

ADD the following to SP 62, Engineer's Field Facilities:

"No field vehicle will be furnished."

The following serves as a **clarification**:

"There is no separate pay item for "Blow Off", please refer to DCWASA specification 2610-11(G). The "Blow Off" is included as part of the work exclusive of gate valve and valve casing. The valve and valve casing are separate bid items that are included in the contract."

PLANS

REPLACE Summary of Quantities on Sheet 125R with attached Summary of Quantities.

Addendum No. 7
Reconstruction of F Street, NW
From 17th St To 23rd St

SUMMARY OF QUANTITIES

NO.	DESCRIPTION	UNIT	QUANTITY
1	FURNISH AND INSTALL TYPE 336S CONTROLLER CABINET FOUNDATION	EA	5
2	FURNISH AND INSTALL TYPE 336S CONTROLLER CABINET	EA	5
3	REMOVE TYPE 336S CONTROLLER CABINET AND FOUNDATION	EA	4
4	FURNISH AND INSTALL TYPE 170 CONTROLLER	EA	5
5	REMOVE TYPE 170 CONTROLLER	EA	4
6	FURNISH AND INSTALL 12 PAIR COMMUNICATION CABLE	LF	4,105
7	FURNISH AND INSTALL TRAFFIC SIGNAL OR STREET LIGHT POLE FOUNDATION	EA	24
8	FURNISH AND INSTALL 20 FOOT (6 M) TALL STEEL TRAFFIC SIGNAL POLE WITH TRANSFORMER BASE	EA	29
9	FURNISH AND INSTALL NO. 18 CAST IRON POST AND CASING	EA	9
10	FURNISH AND INSTALL TWIN NO. 20 STEEL/CAST IRON POST AND CASING	EA	1
11	REMOVE EXISTING POLE (ANY TYPE) AND FOUNDATION	EA	22
12	REMOVE LUMINAIRE FROM STEEL POLE	EA	2
13	FURNISH AND INSTALL 8 FOOT (2.5 M) LONG MAST ARM	EA	7
14	FURNISH AND INSTALL 2 CONDUCTOR 8 AWG STRANDED GROUND WIRE	LF	249
15	FURNISH AND INSTALL 1 CONDUCTOR 10 AWG STRANDED CABLE	LF	338
16	FURNISH AND INSTALL 1 CONDUCTOR 6 AWG STRANDED CABLE	LF	329
17	RELOCATE TRAFFIC SIGNAL CONTROLLER CABINET TO TEMPORARY, PORTABLE CONCRETE BASE	EA	4
18	FURNISH AND INSTALL TEMPORARY, PORTABLE CONCRETE BASE	EA	23
19	REMOVE TEMPORARY, PORTABLE CONCRETE BASE	EA	29
20	FURNISH RED BALL LED MODULE	EA	29
21	FURNISH YELLOW BALL LED MODULE	EA	29
22	FURNISH GREEN BALL LED MODULE	EA	17
23	FURNISH GREEN ARROW LED MODULE	EA	12
24	FURNISH PORTLAND ORANGE HAND LED MODULE	EA	38
25	FURNISH LUNAR WHITE MAN LED MODULE	EA	38
26	REMOVE EXISTING SIGNAL HEAD (ANY TYPE)	EA	89
27	FURNISH AND INSTALL BACK PLATE FOR 3 SECTION TRAFFIC SIGNAL HEAD ON MAST ARM	EA	7
28	FURNISH AND INSTALL CONVENTIONAL 3 SECTION TRAFFIC SIGNAL HEAD ON POLE (ALL 12")	EA	22
29	FURNISH AND INSTALL CONVENTIONAL 3 SECTION TRAFFIC SIGNAL HEAD ON MAST ARM POLE (ALL 12")	EA	7
30	FURNISH AND INSTALL CONVENTIONAL 2 SECTION PEDESTRIAN SIGNAL HEAD	EA	38
31	FURNISH AND INSTALL 7 CONDUCTOR 14 AWG STRANDED CABLE	LF	5,702
32	FURNISH AND INSTALL SLACK COILED CABLE (50 FEET (15 M) AT EACH TEMPORARY BASE)	EA	24
33	FURNISH AND INSTALL SIGN	EA	48
34	REMOVE EXISTING SIGN	EA	47
35	FURNISH AND INSTALL ELECTRICAL MANHOLE	EA	20
36	FURNISH AND INSTALL FLEXIBLE PLASTIC CONDUIT (50 FEET (15 M) AT EACH TEMPORARY BASE)	EA	24
37	FURNISH AND INSTALL 1 - 2 INCH (50 MM) ELECTRICAL PVC CONDUIT	LF	338
38	FURNISH AND INSTALL 3 - 2 INCH (50 MM) ELECTRICAL PVC CONDUITS	LF	17
39	FURNISH AND INSTALL 1 - 4 INCH (100 MM) ELECTRICAL PVC CONDUIT	LF	585
40	FURNISH AND INSTALL 2 - 4 INCH (100 MM) ELECTRICAL PVC CONDUITS	LF	764
41	FURNISH AND INSTALL 1 - 2 INCH (50 MM), 1 - 4 INCH (100 MM) ELECTRICAL PVC CONDUITS	LF	75
42	FURNISH AND INSTALL 1 - 2 INCH (50 MM), 2 - 4 INCH (100 MM) ELECTRICAL PVC CONDUITS	LF	147
43	FURNISH AND INSTALL THERMOPLASTIC PAVEMENT MARKING, 4 INCH	LF	4,990
44	FURNISH AND INSTALL THERMOPLASTIC PAVEMENT MARKING, 6 INCH	LF	2,535
45	FURNISH AND INSTALL THERMOPLASTIC PAVEMENT MARKING, 12 INCH	LF	622
46	FURNISH AND INSTALL TRAFFIC DRUMS	EA	78
47	PEPCO MATERIAL AND LABOR COST FOR TRAFFIC SIGNAL AND/OR STREET LIGHT WORK	LS	5

Addendum No. 7

Reconstruction of F Street, NW
From 17th St To 23rd St