

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>			1. Contract Number	Page of Pages 1 of 43	
2. Amendment/Modification Number <b>No. 7</b>		3. Effective Date See Block 16C		4. Requisition/Purchase Request No.	
5. Solicitation Caption: Rehab. of 11th St Bridge over D St Railroad			6. Issued By: District Department of Transportation Construction Contract Branch 2000 14th Street, NW, 6th Floor Washington, DC 20009		
7. Administered By (If other than line 6) Procurement Support Branch 2000 14th Street, NW, 3rd Floor Bid Room Washington, DC 20009			Code		
8. Name and Address of Contractor (No. Street, city, country, state and ZIP Code)			<input checked="" type="checkbox"/> 9A. Amendment of Solicitation No. <b>POKA-2006-B-0012-JJ</b> <input type="checkbox"/> 9B. Dated (See Item 11) 4/17/2007 <input type="checkbox"/> 10A. Modification of Contract/Order No. <input type="checkbox"/> 10B. Dated (See Item 13)		
Code		Facility			
<b>11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS</b>					
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input type="checkbox"/> is extended. <input checked="" type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>2</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or fax which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or fax, provided each letter or telegram makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.					
12. Accounting and Appropriation Data (If Required)					
<b>13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14</b>					
A. This change order is issued pursuant to: (Specify Authority) The changes set forth in Item 14 are made in the contract/order no. in item 10A.					
B. The above numbered contract/order is modified to reflect the administrative changes (such as changes in paying office, appropriation date, etc.) set forth in item 14, pursuant to the authority of 27 DCMR, Chapter 36, Section 3601.2.					
C. This supplemental agreement is entered into pursuant to authority of:					
D. Other (Specify type of modification and authority)					
<b>E. IMPORTANT:</b> Contractor <input type="checkbox"/> is not, <input checked="" type="checkbox"/> is required to sign this document and return <u>2</u> copies to the issuing office.					
14. Description of amendment/modification (Organized by UCF Section headings, including solicitation/contract subject matter where feasible.)					
<p>The Current Bid Opening Date of July 12, 2007 is not extended</p> <p><b>The purpose of this Amendment is to address the following:</b></p> <p><b>1. Respond to questions from prospective bidders. 2. Update the Wage Decision</b></p> <p><b>3. Update the Pay Item Schedule</b></p> <p><b>This amendment No. 7 consists of this page and 42 pages attached hereto</b></p> <p><b>NO ADDITIONAL QUESTIONS WILL BE ACCEPTED PER ISSUANCE OF THIS AMENDMENT.</b></p>					
Except as provided herein, all terms and conditions of the document referenced in Item (9A or 10A) remain unchanged and in full force and effect					
15A. Name and Title of Signer (Type or print)			16A. Name of Contracting Officer Jerry M. Carter		
15B. Name of Contractor		15C. Date Signed		16B. District of Columbia	
(Signature of person authorized to sign)				16C. Date Signed 7/2/2007	
				(Signature of Contracting Officer)	

Government of the District of Columbia  
Department of Transportation  
Office of Contracting and Procurement  
2000-14th Street, N.W. 6th Floor  
Washington, D.C. 20009

\*\*\*\*\*

**AMENDMENT NUMBER 7**                      **ISSUED July 2, 2007 42 pages**

Invitation No.                      **POKA-2006-B-0012-JJ**  
Federal Aid Project Nos.:        **BH-2112 (003) and STP-2112 (004)**  
Title:                                    **Rehabilitation of 11<sup>th</sup> Street SW Bridge over  
D Street Railroad and Approach Roadways**

**BIDDERS** shall acknowledge receipt of this addendum on official Bid Form.  
Failure to do so may result in rejection of your bid.

**CURRENT BID OPENING DATE:**                      **July 12, 2007**

**BIDDERS** are informed that the above named project is modified as follows:

**BID FORMS AND PROPOSAL**

**DELETE** Pay Item pages **1R THRU 23R in their entirety** and **REPLACE**  
with Pay Item pages **1RR THRU 23RR** and **ADD** page 24 (**24 pages attached as  
part of this amendment**)

**SPECIFICATIONS**

**DELETE** Special Provision entitled “Decorative Fence” attached to  
Addendum #4 and **REPLACE** with Special Provision entitled “Decorative  
Fence” to the Special Provisions (**1 page attached as part of this amendment #7**).

**DELETE** Special Provision entitled “Adjustment of Price for Asphalt Binder”  
attached to Addendum #4 and **REPLACE** with Special Provision entitled  
“Adjustment of Price for Asphalt Binder” to the Special Provisions (**2 pages  
attached as part of this amendment #7**).

## APPENDICES

**DELETE** General Wage Decision DC070001 Modification No. 3 dated 5/18/07 issued under Amendment No. 4 and **REPLACE** with General Wage Decision DC010001 Modification Number 7 dated June 29, 2007 (**12 pages attached as part of this amendment**)

## PLANS

**CHANGE** on Sheet 4, the quantity of Item 618 292 entitled “Furnish and Install #8 Stranded Ground Wire” to 2,230 LF.

**ADD** the following items on Sheet 4: (Quantities are as shown on sheet four originally)

617 090 Furnish & Install 3 Section Conventional Traffic Signal Head on a Pole (All Lenses 12”) Quantity = 7 Each

617 092 Furnish & Install 4 Section Conventional Traffic Signal Head on a Pole (All Lenses 12”) Quantity = 2 Each

617 096 Furnish & Install 3 Section Conventional Traffic Signal Head on a Mast Arm (All Lenses 12”) Quantity = 2 Each

617 098 Furnish & Install 4 Section Conventional Traffic Signal Head on a Mast Arm (All Lenses 12”) Quantity = 1 Each

617 114 Furnish & Install 2 Section Conventional Pedestrian Signal Head on a pole (12”) Quantity = 8 Each

**ADD** the following items on Sheet 4:

618 310 Furnish & Install #2 Stranded Ground Wire, Quantity = 1216 LF

**DELETE** 2<sup>nd</sup> page of tables entitled “Revised Cable Summary” attached to Addendum #4 and **REPLACE** with page 2R revised tables entitled “Cable Summary” (**1 pages attached as part of this amendment**)

**POKA- 2006- B- 0012- JJ**

2

**Amendment No. 7**

**Rehabilitation of 11<sup>th</sup> Street SW**

**Bridge over D Street Railroad and**

**Approach Roadways**

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) & STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001

0010	000003 Employee Training	2000.000 HR	.	.	.	.
0020	000506 Unassigned Special Item -EACH - CLEAN CATCH BASIN- 316 009	15.000 EACH	.	.	.	.
0030	000506 Unassigned Special Item -EACH - F & I 30" X 30" CHANGEABLE MESSAGE SIGN (CMS- A#6)- 617 159	1.000 EACH	.	.	.	.
0040	000506 Unassigned Special Item -EACH - F & I PCC FOUNDATION FOR ELECTRICAL METE RING CABINET- 617 039	1.000 EACH	.	.	.	.
0050	000506 Unassigned Special Item -EACH - REMOVE EXISTING CATCH BASIN- 311 023	10.000 EACH	.	.	.	.
0060	000506 Unassigned Special Item -EACH - SUPPORT FOR CHANGEABLE MESSAGE SIGN (CMS )- 617 161	1.000 EACH	.	.	.	.
0070	000506 Unassigned Special Item -EACH - TYPE C GUARDRAIL APPROACH END TREATMENT- 605 000	3.000 EACH	.	.	.	.

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) & STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0080	000506 Unassigned Special Item -EACH - VARIABLE MESSAGE SIGN (VMS-A#2)- 617 165	1.000 EACH	.		.	
0090	000506 Unassigned Special Item -EACH - VARIABLE MESSAGE SIGN (VMS-B#2)- 617 163	1.000 EACH	.		.	
0100	000509 Unassigned Special Item -LF - CLEAN CATCH BASIN CONNECTION PIPE- 316 011	375.000 LF	.		.	
0110	000509 Unassigned Special Item -LF - F & I 1-3 INCH PVC ENCASED ELECTRICAL CO NDUIT - 617 013	1540.000 LF	.		.	
0120	000509 Unassigned Special Item -LF - F & I 2-3 INCH PVC ENCASED ELECTRICAL CO NDUIT- 617 015	215.000 LF	.		.	
0130	000509 Unassigned Special Item -LF - F & I 2-4 INCH PVC ENCASED ELECTRICAL CO NDUIT- 617 017	10.000 LF	.		.	
0140	000509 Unassigned Special Item -LF - F & I 5-4 INCH & ONE 2" PVC ENCASED ELEC TRICAL CONDUIT- 617 035	50.000 LF	.		.	
0150	000509 Unassigned Special Item -LF - F& I 6-4" & TWO 2" PVC ENCASED ELECTRICAL CONDUIT- 617 037	10.000 LF	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0160	000509 Unassigned Special Item -LF - FURNISH & INSTALL 2-2" & 2-4" PVC ENCASE D ELECTRICAL CONDUIT- 617 031	5.000 LF	.	.	.	.
0170	000509 Unassigned Special Item -LF - REPAIR TYPE 3- CRACK REPAIR - 716 007	1010.000 LF	.	.	.	.
0180	000511 Unassigned Special Item -LS - 618 130 REMOVE TRAFFIC SIGNAL POLE AND T RAFFIC SIGNAL EQUIPMENT	LUMP	LUMP	.	.	.
0190	000511 Unassigned Special Item -LS - DEMOLITION- 205 008	LUMP	LUMP	.	.	.
0200	000511 Unassigned Special Item -LS - MODIFY EXISTING RAILING- 709 013	LUMP	LUMP	.	.	.
0210	000511 Unassigned Special Item -LS - SPLICE CONTROL & COMMUNICATION CABLE(FOC )- 617 007	LUMP	LUMP	.	.	.
0220	000514 Unassigned Special Item -SF - REPAIR TYPE 1- CONCRETE REPAIR- 716 003	990.000 SF	.	.	.	.
0230	000514 Unassigned Special Item -SF - REPAIR TYPE 2- CONCRETE PATCH- 716 005	180.000 SF	.	.	.	.

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0240	000517 Unassigned Special Item -VLF - VACCUM EXCAVATIONS- 212 003	VLF 50.000	.	.	.	.
0250	108002 Progress Photographs	LUMP	LUMP	.	.	.
0260	108004 As-Built Drawings	LUMP	LUMP	.	.	.
0270	200008 Earthwork and Excavation Special Item - LS - GEOSYNTHETIC REINFORCED SOIL SLOPE SYSTEMS	LUMP	LUMP	.	.	.
0280	200009 Earthwork and Excavation Special Item - SF - TEMPORARY SUPPORT OF EXCAVATION- 205 003	SF 1900.000	.	.	.	.
0290	201002 Clear and Grub	LUMP	LUMP	.	.	.
0300	202002 Common Excavation	CY 600.000	.	.	.	.
0310	202004 Hard Surface Pavement Excavation	CY 1550.000	.	.	.	.
0320	204002 Embankment Fill	CY 380.000	.	.	.	.
0330	204004 Borrow Embankment Fill	CY 3439.000	.	.	.	.

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0340	205002 Structure Excavation	1663.000 CY	.		.	
0350	206002 Structure Backfill SP	235.000 CY	.		.	
0360	206991 Structure Backfill Special Item -CY- LIGHTWEIGHT BACKFILL - 206 003	1724.000 CY	.		.	
0370	207002 Trench Excavation and Backfill	665.000 CY	.		.	
0380	207004 Trench Undercut Excavation	75.000 CY	.		.	
0390	207006 Gravel for Trench Undercut	75.000 CY	.		.	
0400	207008 Borrow Trench Backfill	350.000 CY	.		.	
0410	207991 Trench Excavation and Backfill Special Item - CY - TREN.EXCA. -REM. 20" C.I.PIPES, REINFOR. C ON.THROUGH BLOCK, PILES& B.FILL-207 003	65.000 CY	.		.	
0420	209002 Aggregate Base Course	900.000 CY	.		.	
0430	212002 Test Pit	10.000 EACH	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) & STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	302002 Valve Casing	10.000 EACH	.		.	
0450	303002 Abandon Valve Casing	2.000 EACH	.		.	
0460	303004 Remove Fire Hydrant	1.000 EACH	.		.	
0470	304002 Butterfly Valve Manhole	2.000 EACH	.		.	
0480	305002 Ductile Iron Pipe, 4 - 8 Inch	25.000 LF	.		.	
0490	305004 Ductile Iron Pipe, 12 Inch	425.000 LF	.		.	
0500	305018 Extra Fittingd - Contractor Furnished	2000.000 LBS	.		.	
0510	305991 Pipe Water Main - Ductile Iron Special Item - LF - DUCTILE IRON PIPE, 20 INCH (CLASS 52)- 3 05 008	410.000 LF	.		.	
0520	305991 Pipe Water Main - Ductile Iron Special Item - LF - DUCTILE IRON PIPE, 20 INCH (CLASS 56)- 3 05 009	165.000 LF	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) & STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	305991 Pipe Water Main - Ductile Iron Special Item - LF - STEEL CASING PIPE, 30 INCH , AND ACCESSORIES- 305011	80.000 LF	.		.	
0540	306002 Gate Butterfly Valve, 3 - 12 Inch	6.000 EACH	.		.	
0550	306006 Gate Butterfly Valve, 20 Inch	2.000 EACH	.		.	
0560	306991 Gate Butterfly Valve Special Item - EACH - FURNISH & INSTALL AIR VALVE- 306001	2.000 EACH	.		.	
0570	307002 Set Fire Hydrant	1.000 EACH	.		.	
0580	309002 Sewer Manhole on Sewer 48 Inch and Less Dia.	11.000 VLF	.		.	
0590	310008 Basin Connect PCC Pipe, Class III, 15 Inch	225.000 LF	.		.	
0600	310992 Catch Basins Special Item -EACH - DUAL INLET WATER QUALITY BASIN- 310 025	11.000 EACH	.		.	
0610	311002 Adjust Sewer-Water-Utility Manhole Frame	15.000 EACH	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0620	311016 Furnish Sewer-Water Manhole Frame	15.000 EACH	.		.	
0630	313002 Abandon Basin Connecting Pipe	8.000 EACH	.		.	
0640	313006 Abandon Basin	3.000 EACH	.		.	
0650	314004 PCC Pipe, Class III, Gasket, 15 Inch SP	35.000 LF	.		.	
0660	324002 PCC In-Line Thrust Block	1.000 EACH	.		.	
0670	324991 PCC In-Line Thrust Block Special Item - EACH - SP	4.000 EACH	.		.	
0680	402012 Sperrpave Surface Course, 12.5 mm	210.000 TON	.		.	
0690	402991 Hot Bituminous Pavement Special Item - TON - SUPERPAVE LEVELING COURSE, 9.5 MM - 402 006	790.000 TON	.		.	
0700	403002 Tack Coat	7300.000 SY	.		.	
0710	407991 Temporary AC Special Item - TON - TEMPORARY AC, SUPERPAVE 9.5 MM LEVELING COURSE - 407 006	330.000 TON	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0720	409002 Asphalt Patching, Superpave Surface Course, 12.5 mm	10.000 TON	.		.	
0730	409991 Asphalt Patching Special Item - TON - ASPHALT PATCHING, SUPERPAVE LEVELING CO URSE, 9.5 MM - 409 006	40.000 TON	.		.	
0740	501008 Reinforced PCC Pavement, 10 Inch	3200.000 SY	.		.	
0750	502992 Portland Cement Concrete Base Special Item -SY - PCC BASE FOR UTILITY CUTS- 502 004	105.000 SY	.		.	
0760	605002 W Beam Guiderail	335.000 LF	.		.	
0770	605026 Thrie Beam Terminal Connector SP	2.000 EACH	.		.	
0780	605028 Thrie Beam Transition Panel SP	2.000 EACH	.		.	
0790	605038 Remove W Beam/Thrie Beam Guiderail	125.000 LF	.		.	
0800	605991 Steel Guiderails Special Item - EACH W BEAM TRAILING END TERMINAL- 605 021	2.000 EACH	.		.	
0810	606002 Pavement Profiling (Milling)	2050.000 SY	.		.	

SCHEDULE OF ITEMS

DATE:  
REVISED:

CONTRACT ID: KA2006B0012JJ PROJECT(S): BH-2112 (003) & STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0820	607991 Misc. Fencing Special Item - LF - DECORATIVE FENCE	1000.000 LF	.		.	
0830	608004 PCC Sidewalk, 4 Inch	875.000 SY	.		.	
0840	609068 Furnish and Set 8"x12" Granite Straight Curb	1650.000 LF	.		.	
0850	609072 Furnish and Set 8"x12" Granite Circular Curb, Radius 10-100 Ft.	100.000 LF	.		.	
0860	609200 PCC Wheelchair/Bicycle Ramp - New Construction	4.000 EACH	.		.	
0870	609993 Curb, Gutter, & Paved Flume Special Item - LF - FURNISH & SET GRANITE CIR. CURB, RADIUS > 100', SPECIAL- 609 079	140.000 LF	.		.	
0880	609993 Curb, Gutter, & Paved Flume Special Item - LF - FURNISH & SET GRANITE STRAIGHT CURB, SPECIAL- 609 077	800.000 LF	.		.	
0890	609993 Curb, Gutter, & Paved Flume Special Item - LF - FURNISH AND SET 8"X12" MODIFIED GRANITE STRAIGHT CURB- 609 069	1300.000 LF	.		.	
0900	610004 Seed with 4 Inch Topsoil	2300.000 SY	.		.	

SCHEDULE OF ITEMS

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) & STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0910	611084 Wheel Stop	40.000 EACH	.		.	
0920	612002 Mobilization	LUMP	LUMP		.	
0930	614012 Portable Precast PCC Barrier	1700.000 LF	.		.	
0940	614992 PCC Traffic Barriers Special Item - LF - RELOCATE PORTABLE PRECAST PCC BARRIER- 6 14 014	3200.000 LF	.		.	
0950	616004 Construction Lane Closing	LUMP	LUMP		.	
0960	616006 Remove Lane Markings	3750.000 SF	.		.	
0970	616008 Temporary Construction Sign Supports	25.000 EACH	.		.	
0980	616012 Construction Warning and Detour Signs	400.000 SF	.		.	
0990	616016 Flashing Amber Warning Lights, Type "B"	20.000 EACH	.		.	
1000	616022 Construction Sign Warning Flags	2.000 EACH	.		.	

SCHEDULE OF ITEMS

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) & STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1010	616024 Type III PVC Barricade	4.000 EACH	.		.	
1020	616028 Traffic Drums	30.000 EACH	.		.	
1030	616030 Single-Faced White Raised Reflective Pavement Markers	82.000 EACH	.		.	
1040	616040 Thermoplastic Pavement Marking, 4 Inch	800.000 LF	.		.	
1050	616042 Thermoplastic Pavement Marking, 4 Inch Dash	100.000 LF	.		.	
1060	616044 Thermoplastic Pavement Marking, 6 Inch	500.000 LF	.		.	
1070	616050 Thermoplastic Pavement Marking, 12 Inch	150.000 LF	.		.	
1080	616060 Painted Lane Marking, 4 Inch	6100.000 LF	.		.	
1090	616090 Construction Zone Attenuator	8.000 EACH	.		.	
1100	616992 Traffic Control Special Item - EACH - DOUBLE-FACED WHITE/RED RAISED REFLECTIVE PAVEMENT MARKERS- 616034	5.000 EACH	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1110	616992 Traffic Control Special Item - EACH - PERMANENT PREFORMED PAVEMENT MARKING ARR OW- 616 055	EACH 2.000	.		.	
1120	616992 Traffic Control Special Item - EACH - PERMANENT PREFORMED PAVEMENT MARKING LET TER- 616 053	EACH 4.000	.		.	
1130	616994 Traffic Control Special Item - LF - PREFORMED HIGH CONTRAST TAPE, 4 INCH - 6 16 057	LF 1900.000	.		.	
1140	616994 Traffic Control Special Item - LF - PREFORMED PATTERNED TAPE, 12 INCH- 616 063	LF 400.000	.		.	
1150	616994 Traffic Control Special Item - LF - PREFORMED PATTERNED TAPE, 6 INCH- 616 061	LF 1250.000	.		.	
1160	617006 Remove Abandoned Traffic Signal Or Street Light Pole Foundat ion	EACH 17.000	.		.	
1170	617014 Furnish And Install One 2 Inch Pvc Encased Electrical Conduit	LF 15.000	.		.	
1180	617018 Furnish And Install No. 10 Awg Stranded Wire	LF 1589.000	.		.	
1190	617020 Furnish And Install No. 8 Awg Stranded Wire	LF 5493.000	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1200	617024 Furnish And Install Galvanized Steel Transformer Base	13.000 EACH	.		.	
1210	617028 Furnish And Install Handbox	1.000 EACH	.		.	
1220	617032 Furnish And Install One 2 Inch And One 4 Inch Pvc Encased El ectrical Conduits	45.000 LF	.		.	
1230	617034 Furnish And Install Four 4 Inch Pvc Encased Electrical Condu its	175.000 LF	.		.	
1240	617038 Furnish And Install Pcc Foundation For Controller Cabinet	1.000 EACH	.		.	
1250	617042 Furnish Temporary, Portable, Concrete Base For 20 Foot Steel Traffic Signal Pole Mounted On A Transformer Base	6.000 EACH	.		.	
1260	617046 Furnish And Install 20 Foot Tall Steel Traffic Signal Pole	4.000 EACH	.		.	
1270	617048 Furnish And Install 8 Foot Long Mast Arm With Clamp And Remo veable End Cap	2.000 EACH	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1280	617050 Furnish And Install 7 Conductor 14 Awg Stranded Electrical T raffic Signal Cable	2100.000 LF	.		.	
1290	617058 Furnish And Install 25 Pair 19 Awg Underground Communication s Cable	1200.000 LF	.		.	
1300	617068 Furnish Red Ball Led Module	9.000 EACH	.		.	
1310	617070 Furnish Yellow Ball Led Module	9.000 EACH	.		.	
1320	617072 Furnish Green Ball Led Module	9.000 EACH	.		.	
1330	617078 Furnish Green Arrow Led Module	1.000 EACH	.		.	
1340	617084 Furnish 12 Inch Overlay Lunar White Walking Person And Portl and Orange Raised Hand Led Module	6.000 EACH	.		.	
1350	617086 Furnish 12 Inch Portland Orange Countdown Led Module	6.000 EACH	.		.	
1360	617090 Furnish And Install 3 Section Conventional Traffic Signal He ad On A Pole (All Lenses 12?)	7.000 EACH	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1370	617092 Furnish And Install 4 Section Conventional Traffic Signal Head On A Pole (All Lanes 12?)	EACH 2.000	.		.	
1380	617096 Furnish And Install 3 Section Conventional Traffic Signal Head On A Mast Arm (All Lenses 12?)	EACH 2.000	.		.	
1390	617098 Furnish And Install 4 Section Conventional Traffic Signal Head On A Mast Arm (All Lanes 12?)	EACH 1.000	.		.	
1400	617114 Furnish And Install 2 Section Conventional Pedestrian Signal Head On A Pole (12?)	EACH 8.000	.		.	
1410	617124 Furnish And Install Traffic Signal Controller And Cabinet	EACH 1.000	.		.	
1420	617126 Remove Abandoned Traffic Signal Controller Cabinet Foundatio n	EACH 1.000	.		.	
1430	617128 Remove Street Light Pole And Street Light Equipment	EACH 11.000	.		.	
1440	617132 Remove Traffic Signal Controller And Cabinet	EACH 1.000	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1450	617164 Traffic Sign Panels	115.000 SF	.		.	
1460	618002 Electrical Work PROBE DISCOVERY OF FAULTS (VMS, CMS, AND EQUIPMENT)- 618 003	LUMP	LUMP			.
1470	618022 Furnish and Install 48" x 48" x 48" Manhole	15.000 EACH	.		.	
1480	618038 Furnish and Install Frame and Cover for 48" x 48" Manhole	15.000 EACH	.		.	
1490	618050 Clean Electrical Manhole/Handhole	17.000 EACH	.		.	
1500	618052 Remove Hazardous Waste Materials from Manhole/Handhole	17.000 EACH	.		.	
1510	618140 Remove Electrical Conduit	25.000 LF	.		.	
1520	618250 Furnish and Install #0000 Stranded Wire	4628.000 LF	.		.	
1530	618292 Furnish and Install #8 Stranded Ground Wire	3435.000 LF	.		.	
1540	618310 Furnish and Install #2 Stranded Ground Wire	1216.000 LF	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1550	618394 Furnish and Install 15" B.C. Street Light Foundation	13.000 EACH	.		.	
1560	618454 Remove Steel Transformer Base	11.000 EACH	.		.	
1570	618548 Furnish and Install 28'-6" Steel Pendant Pole with Truss Arm	16.000 EACH	.		.	
1580	618778 Furnish and Install 400 Watt HPS Tear Drop Fixture	16.000 EACH	.		.	
1590	618824 Remove Fixture, Any Type	5.000 EACH	.		.	
1600	618910 Furnish and Install Ground Rod	30.000 EACH	.		.	
1610	618918 Furnish and Install Electrical Equipment for Underpass	1.000 EACH	.		.	
1620	618928 Furnish and Install Electrical Junction Box	6.000 EACH	.		.	
1630	618936 Furnish and Install Electrical Equipment Cabinet METER & DISCONNECT SWITCH)	1.000 EACH	.		.	
1640	618942 Remove Electrical Equipment Cabinet	1.000 EACH	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1650	618944 Ground Testing	LUMP	LUMP			.
1660	618946 Cable Insulation Testing	LUMP	LUMP			.
1670	618992 ELECTRICAL WORK SPECIAL ITEM -EACH- FURNISH & INSTALL FIXTURE ANY TYPE ( 250 WATT WALL PACK)- 618 821	EACH	6.000			.
1680	618993 ELECTRICAL WORK SPECIAL ITEM -LF- CLEAN & ROD EXISTING CONDUIT (FOR COMMUN ICATION CABLE)- 618 173	LF	1100.000			.
1690	618993 ELECTRICAL WORK SPECIAL ITEM -LF- CLEAN & ROD EXISTING CONDUIT (FOR STREET LIGHT CABLE)- 618 175	LF	105.000			.
1700	618993 ELECTRICAL WORK SPECIAL ITEM -LF- F & I 1- 3/4" & 1-2" FRE ENCASED ELECTRI CAL CONDUIT- 618 077	LF	45.000			.
1710	618993 ELECTRICAL WORK SPECIAL ITEM -LF- F & I 1-2" FRE ENCASED ELECTRICAL CONDUIT- 618 079	LF	205.000			.
1720	618993 ELECTRICAL WORK SPECIAL ITEM -LF- F & I 2-2" PVC ENCASED ELECTRICAL CONDUIT (BRIDGE PARAPET)- 618 085	LF	615.000			.

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1730	618993 ELECTRICAL WORK SPECIAL ITEM -LF- F & I 2-3" FRE ENCASED ELECTRICAL CONDUIT- 618 081	185.000 LF	.		.	
1740	618993 ELECTRICAL WORK SPECIAL ITEM -LF- F& I 2-3" PVC COATED STEEL CONDUIT ( SUS PENDED FROM STRUCTURE)- 618 083	120.000 LF	.		.	
1750	618993 ELECTRICAL WORK SPECIAL ITEM -LF- FUR. & INSL. 1-1" PVC COATED STEEL ELECT .L CONDUIT (SURFACE MOUNTED)- 618 071	165.000 LF	.		.	
1760	618993 ELECTRICAL WORK SPECIAL ITEM -LF- FURNISH & INSTALL #10 STRANDED GROUND WI RE- 618 293	270.000 LF	.		.	
1770	618993 ELECTRICAL WORK SPECIAL ITEM -LF- FURNISH & INSTALL 2-2" PVC ENCASED ELECT RICAL CONDUIT- 618 087	45.000 LF	.		.	
1780	618993 ELECTRICAL WORK SPECIAL ITEM -LF- FURNISH & INSTALL CONTROL & COMMUNICATIO N CABLE (FOC)- 618 005	4000.000 LF	.		.	
1790	618993 ELECTRICAL WORK SPECIAL ITEM -LF- FURNISH & INSTALL ONE 1 1/2" CONDUIT ( L IGHTS ON BRIDGE STRUCTURE)- 618 075	10.000 LF	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1800	618993 ELECTRICAL WORK SPECIAL ITEM -LF- FURNISH & INSTALL ONE 1 1/4" CONDUIT (LIGHTS ON BRIDGE STRUCTURE)- 618 073	10.000 LF	.	.	.	.
1810	618993 ELECTRICAL WORK SPECIAL ITEM -LF- FURNISH & INSTALL ONE 3/4" ENCASED ELECTRICAL CONDUIT- 618 069	100.000 LF	.	.	.	.
1820	618993 ELECTRICAL WORK SPECIAL ITEM -LF- REMOVE COMMUNICATION CABLE- 618 193	1100.000 LF	.	.	.	.
1830	618993 ELECTRICAL WORK SPECIAL ITEM -LF- REPAIR OF EXISTING CONDUIT (STREET LIGHT & TRAFFIC SIGNAL WORK)- 618 179	20.000 LF	.	.	.	.
1840	618999 Payment to PEPCO for Connection, Disconnection, Inspection INSPECTION	LUMP	LUMP		70000.00	
1850	620002 Timber Ground Mounted Sign Posts, 4x4 Inch	32.000 LF	.	.	.	.
1860	620004 Timber Ground Mounted Sign Posts, 4x6 Inch	235.000 LF	.	.	.	.
1870	620006 Timber Ground Mounted Sign Posts, 6x6 Inch	40.000 LF	.	.	.	.

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1880	620012 Guide Sign Panels	85.000				
		SF	.		.	
1890	620032 Remove Existing Ground Mounted Sign	85.000				
		SF	.		.	
1900	620040 Federal Aid Project Sign	2.000				
		EACH	.		.	
1910	620993 Traffic Signing Special Item - EACH - REMOVE EXISTING OVERHEAD SIGNS ( CHANGEA BLE MESSAGE SIGN)- 620 031	1.000				
		EACH	.		.	
1920	620993 Traffic Signing Special Item - EACH - REMOVE EXISTING OVERHEAD SIGNS ( VARIABL E MESSAGE SIGN)- 620 029	2.000				
		EACH	.		.	
1930	624002 Engineer's Field Facilities					
		LUMP		LUMP		.
1940	625002 Field Layout					
		LUMP		LUMP		.
1950	626002 Protection Shield					
		LUMP		LUMP		.
1960	628002 Erosion and Sediment Control					
		LUMP		LUMP		.
1970	703002 PCC Footing	36.000				
		CY	.		.	

## SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: KA2006B0012JJ

PROJECT(S): BH-2112 (003) &amp; STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1980	703006 PCC Pier-Abutment-Wall	560.000 CY	.		.	
1990	703008 PCC Superstructure	463.000 CY	.		.	
2000	703014 PCC Approach Slab	235.000 CY	.		.	
2010	703991 Concrete for Structures Special Item - CY - PCC MOMENT SLAB- 703 015	300.000 CY	.		.	
2020	704004 Epoxy Coated Reinforcement Bars	250000.000 LBS	.		.	
2030	706006 Structural Steel - AASHTO M270, Grade 50	295500.000 LBS	.		.	
2040	706020 Bridge Bearings, (Each)	50.000 EACH	.		.	
2050	706993 Structural Steel Special Item - LS - UTILITY SUPPORTS ON BRIDGE- 706 031	LUMP	LUMP		.	
2060	707002 Paint New Metalwork	LUMP	LUMP		.	
2070	708004 Stone Masonry, Class B	200.000 CF	.		.	

SCHEDULE OF ITEMS

DATE:  
REVISED:

CONTRACT ID: KA2006B0012JJ PROJECT(S): BH-2112 (003) & STP-2112 (004)

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
2080	708011 Reset Stone Masonry	1000.000 CF	.		.	
2090	708013 Repoint Stone Masonry	1000.000 LF	.		.	
2100	709012 Aluminum Railing	428.000 LF	.		.	
2110	709991 Railing Special Item - LF - ORNAMENTAL FENCE- 709 015	248.000 LF	.		.	
2120	717002 Armored Joint with Neoprene Strip Seal	281.000 LF	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	

## **DECORATIVE FENCE, Item 607 991**

**A. DESCRIPTION** – This work includes the fabricating, furnishing, assembling, and erecting of decorative ground mounted fence in conformance with these Special Provisions, the Plans, Specifications, or as directed by the Engineer. The design and architectural details shall be in the spirit of what is described here and coordinated with the existing fence to the east of Road E and north of the proposed bridge. The Contractor shall submit shop drawings and catalog sheets for approval.

The decorative fence shall be used throughout the project wherever the Contractor is required to remove and replace existing chainlink fence.

The system shall meet the following requirements:

- 8'-0" tall
- 8'-0" maximum post spacing
- 1" square pickets
- Clear space between pickets shall not exceed 3"
- 1.75" square rails
- 3" square posts
- Post caps shall be provided for all posts.
- Brown color
- 3'-0" minimum post embedment. Post hole shall be backfilled with 3500 psi concrete. Hole diameter shall be 1'-0" minimum.
- The fence shall receive a fusion bonded polyester or similar coating. Painting shall not be acceptable.
- All connections shall be tamper resistant.
- Fence shall be capable of carrying a 600 lb load applied at midspan of a panel without permanent deformation.

**B. SUBMITTALS** – The contractor shall submit for approval shop drawings and catalog sheets for the proposed fence system. Submittals shall include but not be limited to the following information:

- Materials
- Finish
- Post embedment and foundation details
- Assembly and construction details

**C. CONSTRUCTION** – All posts and pickets shall be plumb. Appropriate foundations shall be provided per the Manufacturer's recommendations. The fence shall be capable of accommodating thermal expansion and contraction. The bottom of the fence shall be held as uniformly as is practical to 2" above the finished grade. Any excavation or backfill required to comply with the above clearance shall be as approved by the Engineer.

**D. MEASUREMENT AND PAYMENT** – The unit of measure for DECORATIVE FENCE will be per linear foot. Payment will be made at the contract unit price per linear foot and will constitute full compensation for all materials, labor, tools, equipment, and incidentals necessary to complete the work.

## **SP ADJUSTMENT OF PRICE FOR ASPHALT BINDER**

An adjustment will be made to the Contract unit price of Hot Mix Asphalt items if the price of asphalt fluctuates significantly from the prevailing price set by D-DOT as base price or quoted in the Contract Documents to the date of placement. The contract unit price will be adjusted by the amount of fluctuation above 5 percent for Contracts scheduled to be paved during more than one construction season or having an estimated mix quantity of 10000 tons or more. For Contracts completed within one construction season and having an estimated mix quantity of less than 10000 tons, the adjustment will be based upon the amount of fluctuation more than +/- 15 percent. Only the differential percent change beyond the above noted 5 and 15 percent will be used.

For the purpose of making these calculations, a monthly price index will be maintained by D-DOT. This index will be the average F.O.B. selling price of asphalt binder as published by Maryland Asphalt Association. For information concerning the Maryland Price Index of asphalt binder for each month, see web site [www.mdasphalt.org](http://www.mdasphalt.org).

The adjusted Contract unit price of Hot Mix Asphalt will be computed monthly by using the following formula:

$$F = (PP-PB)/PB \times 100$$

Where:

F = percent price increase/decrease of asphalt binder.

PP = index price of asphalt binder per ton at placement month, and

PB = prevailing index price of asphalt binder per ton as specified in the contract or as fixed by D-DOT.

Adjusted Contract unit price due Contractor when price of asphalt binder increases

$$A = B + ( D \times T \times PB )$$

Adjusted Contract unit price due D-DOT when price of asphalt binder decreases:

$$A = B - ( D \times T \times PB )$$

Where:

A= adjusted contract unit price per ton of Hot Mix Asphalt

B = Contract unit price per ton of Hot Mix Asphalt

D = differential percentage expressed as a decimal (F-5 percent or F-15 percent as defined above)

T = Design target asphalt content expressed as a decimal

PB= prevailing index price of asphalt binder per ton as specified in the contract or as fixed by D-DOT.

- A. The asphalt binder price adjustment will be calculated monthly by the Chief Engineer.
- B. The Adjustment of Price for Asphalt Binder will be denied for any placement beyond the completion date.

General Decision Number: DC070001 06/22/2007 DC1

Superseded General Decision Number: DC20030001

State: District of Columbia

Construction Types: Heavy (Heavy and Sewer and Water Line) and Highway

County: District of Columbia Statewide.

HEAVY CONSTRUCTION PROJECTS (Including Sewer and Water Lines);  
HIGHWAY CONSTRUCTION PROJECTS

Modification Number	Publication Date
0	02/09/2007
1	05/04/2007
2	05/11/2007
3	05/18/2007
4	06/08/2007
5	06/15/2007
6	06/22/2007

ASBE0024-001 10/01/2006

	Rates	Fringes
Asbestos Worker/Heat and Frost Insulator Includes the application of all insulating materials, protective coverings, coatings and finishes to all types of mechanical systems.....	\$ 27.13	13.13

ASBE0024-002 10/01/2006

	Rates	Fringes
Hazardous Material Handler Includes preparation, wetting, stripping, removal, scrapping, vacuuming, bagging and disposing of all insulation materials, whether they contain asbestos or not, from mechanical systems.....	\$ 18.00	6.45

ASBE0024-005 10/01/2006

Rates	Fringes
-------	---------

Fire Stop Technician

Includes the application of materials or devices within or around penetrations and openings in all rated wall or floor assemblies, in order to prevent the passage of fire, smoke or other gases. The application includes all components involved in creating the rated barrier at perimeter slab edges and exterior cavities, the head of gypsum board or concrete walls, joints between rated wall or floor components, sealing of penetrating items and blank openings.....\$ 22.00 6.24

-----  
BOIL0193-001 10/01/2006

	Rates	Fringes
BOILERMAKER.....	\$ 32.06	16.46

-----  
\* BRDC0001-001 04/30/2007

	Rates	Fringes
Bricklayer.....	\$ 25.90	6.19

-----  
CARP0132-001 05/01/2007

	Rates	Fringes
Carpenter/Lather.....	\$ 24.37	6.15
Piledriver.....	\$ 22.87	6.85

-----  
CARP0132-003 05/01/2004

	Rates	Fringes
Diver Tender.....	\$ 20.85	5.50
Diver.....	\$ 29.63	5.50

-----  
CARP1831-001 04/01/2003

	Rates	Fringes
Millwright.....	\$ 24.34	4.05

-----  
ELEC0026-001 06/04/2007

	Rates	Fringes
--	-------	---------

Electrician.....\$ 33.45 11.35+a

a. PAID HOLIDAYS: New Year's Day, Martin Luther King Jr.'s Birthday, Inauguration Day, Memorial Day, Fourth of July, Labor Day, Veterans Day, Thanksgiving Day, the day after Thanksgiving and Christmas Day or days designated as legal holidays by the Federal Government.

-----  
ELEC0026-008 07/01/2003

	Rates	Fringes
Motor Repairmen		
Removal and reinstallation		
of electrical motors.....	\$ 23.69	7.73+3%+a

a. PAID HOLIDAYS:  
New Year's Day, Martin Luther King Jr.'s Birthday, Inauguration Day, Memorial Day, Fourth of July, Labor Day, Veterans Day, Thanksgiving Day, the day after Thanksgiving and Christmas Day or days designated as legal holidays by the Federal Government.

-----  
ELEC0070-001 01/01/2006

	Rates	Fringes
Line Construction:		
Groundmen.....	\$ 12.03	4.75+18.75%
Linemen, Cable Splicers,		
Equipment Operators.....	\$ 25.50	4.75+18.75%
Truck with winch.....	\$ 12.35	4.75+18.75%

-----  
ENGI0077-001 05/01/2007

	Rates	Fringes
Power equipment operators:		
(HEAVY AND HIGHWAY		
CONSTRUCTION)		
GROUP 1.....	\$ 27.64	6.82+a
GROUP 2.....	\$ 27.18	6.82+a
GROUP 3.....	\$ 26.47	6.82+a
GROUP 4.....	\$ 24.44	6.82+a
GROUP 5.....	\$ 19.90	6.82+a
GROUP 6.....	\$ 29.01	6.82+a

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: 35 ton cranes & above, tower & climbing cranes, derricks, concrete boom pump, drill rigs (equivalent to L & Double L), mole.

GROUP 2: Backhoes, cableways, cranes, cherry pickers, elevating graders, hoists, paving mixers, power shovels, tunnel shovels. batch plants, shields, tunnel

mining machines, gradalls, front end loaders, 3 1/2 cu. yds. and above, power driven wheel scoops and scrapers (50 cu. yds. struck capacity or above), rail tamper, draglines, boomcat, mucking machines, graders in tunnels, pile driving engines.

GROUP 3: Front end loaders below 3 1/2 cu. yds, boom trucks, hydraulic backhoes 1/2 yds. capacity or below rubber or track mounted, tug boats, power driven wheel scoops & scrapers, blade graders, motor graders, bulldozers, trenching machines, concrete mixer, speed swing pettibone, ballast regulator, concrete pump, mechanic, welder, mechanic welder, shotcrete machines, Hoeram, locomotive (standard, narrow gauge), tuggers.

GROUP 4: High lifts above 10 feet, boilers (skelton), asphalt spreaders, bullfloat finishing machines, concrete finishing machines, concrete spreaders, fine graders, air compressors, welding machines, pumps, generators, well points, deep wells, hydraulic pumps, elevators, freeze uniits, tunnel motorman or dinky operator, roller, conveyors, well drilling machines, grout pump, fireman.

GROUP 5: Fork lifts, ditch witch, bobcat 1/3 cu. yd. and below, space heaters, sweepers, assistant engineers, oilers.

GROUP 6: Master mechanic.

a. PAID HOLIDAYS: New Years Day, Inaugural Day, Decoration Day, Independence Day, Labor Day, Martin Luther King's Birthday, Veterans' Day, Thanksgiving Day, Friday after Thanksgiving and Christmas Day.

b. PREMIUM PAY: Tower cranes and cranes 100-ton and over to receive \$1.00 per hour premium over Group One.

-----  
 ENGI0077-002 06/01/2006

	Rates	Fringes
Power equipment operators: (PAVING AND INCIDENTAL GRADING)		
GROUP 1.....	\$ 21.50	5.25
GROUP 2.....	\$ 19.05	5.25
GROUP 3.....	\$ 17.80	5.25
GROUP 4.....	\$ 16.59	5.25
GROUP 5.....	\$ 15.35	5.25
GROUP 6.....	\$ 21.45	5.25

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Gradall operator, Crane.

GROUP 2: Boom Truck, Milling Machine, Excavator, Rubber Tire Backhoe, Asphalt Paver, Asphalt Plant Engineer.

GROUP 3: Motor Grader, Track Loader, Rubber Tire Loader, Track Dozer, Concrete Paver.

GROUP 4: Broom Truck, Asphalt Roller.  
 GROUP 5: Air Compressor, Grade Rollers.  
 GROUP 6: Mechanic.

-----  
 ENGI0077-003 07/01/2006

	Rates	Fringes
Power equipment operators: (SEWER, GAS AND WATER LINE CONSTRUCTION)		
GROUP 1.....	\$ 19.43	5.12+a
GROUP 2.....	\$ 19.03	5.12+a
GROUP 3.....	\$ 18.88	5.12+a
GROUP 4.....	\$ 18.80	5.12+a
GROUP 5.....	\$ 18.69	5.12+a
GROUP 6.....	\$ 18.52	5.12+a
GROUP 7.....	\$ 18.62	5.12+a
GROUP 8.....	\$ 18.52	5.12+a
GROUP 9.....	\$ 19.06	5.12+a
GROUP 10.....	\$ 18.41	5.12+a
GROUP 11.....	\$ 18.29	5.12+a
GROUP 12.....	\$ 18.20	5.12+a

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Backhoes, Cableways, Cranes, Derricks, Draglines, Power Shovels, Tunnel Shovels, Tunnel Mucking Machines (1 cubic yard capacity or above).

GROUP 2: Backhoes, Boom Cats, Cableways, Cranes, Derricks, Draglines, Elevating Graders, Hoists, Paving Mixers, Pile Driving Engines, Power and Tunnel Shovels, Tunnel Mucking Machines, Batch Plant, Concrete Pumps.

GROUP 3: Operators of Hydraulic Backhoes of below 1/2 yard capacity.

GROUP 4. Trenching machines above 83 inches.

GROUP 5: Trenching machines (up to & including 83"), Boilers (Skelton), Well Drilling Machines.

GROUP 6: Air Compressors (Tunnel).

GROUP 7: Front-end Loaders (Hi-Lift) and Bulldozers on Sewer and Water Line Work.

GROUP 8: Concrete Mixers, Power Driven Wheel Scoops and Scrapers, Blade graders, Motor Graders, Tunnel Mechanics, Tunnel Motormen.

GROUP 9: Mechanics.

GROUP 10: Bulldozers, Hydraulic Tamper and Hoe Pack Operators.

GROUP 11: Rollers.

GROUP 12: Air Compressors, Pumps, Welding Machines, Well Points.

a. PAID HOLIDAYS: New Year's Day, Inaugural Day, Washington's Birthday, Decoration Day, Independence Day, Labor Day, Veterans Day, Thanksgiving Day, Christmas Day and Martin Luther King's Birthday.

-----  
 IRON0005-001 06/01/2006

	Rates	Fringes
Ironworkers:		
Structural, Ornamental and Chain Link Fence.....	\$ 25.68	11.345

-----  
 IRON0201-001 05/01/2007

	Rates	Fringes
Ironworkers:		
Reinforcing.....	\$ 24.80	12.08

-----  
 LABO0456-006 06/01/2006

	Rates	Fringes
Laborers: (BRICK MASONRY WORK)		
Mason Tenders.....	\$ 13.91	3.84
Scaffold Builders, Mortarmen and Small Equipment Operators.....	\$ 14.65	3.84

-----  
 LABO0657-003 06/01/2006

	Rates	Fringes
Laborers: (HEAVY AND HIGHWAY AND SEWER & WATER LINES CONSTRUCTION)		
GROUP 1.....	\$ 19.18	3.84
GROUP 2.....	\$ 19.46	3.84
GROUP 3.....	\$ 19.61	3.84
GROUP 4.....	\$ 19.75	3.84
GROUP 5.....	\$ 20.15	3.84
GROUP 6.....	\$ 20.64	3.84
GROUP 7.....	\$ 21.11	3.84
GROUP 8.....	\$ 21.77	3.84

LABORERS CLASSIFICATIONS:

GROUP 1: Carloaders, choker setter, concrete crewman, crushed feeder, demolition laborers, including salvaging all material, loading, cleaning up, wrecking, dumpmen, flagmen, fence erector and installer (other than chain link), including installation and erection of fence, guard rails, medial rails, reference posts, guide posts and right-of-way markers, form

strippers, general laborers, railroad track laborers, riprap man, scale man, stake jumper, structure mover, includes foundation, separation, preparation, cribbing, shoring, jacking and unloading of structures, water nozzleman, timber buckler and faller, truck loader, water boys, tool room men.

GROUP 2: Combined air and water nozzleman, cement handler, dope pot fireman (nonmechanical), form cleaning machine, mechanical railroad equipment (includes spiker, puller, tile cleaner, tamper, pipe wrapper, power driven wheelbarrows, operators of hand derricks, towmasters, scootcretes, buggymobiles and similar equipment), tamper or rammer operator, trestle scaffold builders over one tier high, power tool operator (gas, electric or pneumatic), sandblast or gunnite tailhose man, scaffold erector, (steel or wood), vibrator operator (up to 4 feet), asphalt cutter, mortar men, shorer and lagger, creosote material handler, corrosive enamel or equl, paver breaker and jackhammer operators.

GROUP 3: Multi-section pipe layer, non-metallic clay and concrete pipe layer (including caulker, collarman, jointer, rigger and jacker, thermal welder and corrugated metal culvert pipe layer.

GROUP 4: Asphalt block pneumatic cutter, asphalt roller, walker, chainsaw operator with attachment, concrete saw (walking), high scalers, jackhammer operator (using over 6 feet of steel), vibrator operator (4 feet and over), well point installer, air trac operator.

GROUP 5: Asphalt screeder, big drills, cut of the hole drills (1 1/2 " piston or larger), down the hole drills (3 1/2" piston or larger) gunnite or sandblaster nozzleman, asphalt raker, asphalt tamper, form setter, demolition torch operator, shotcrete nozzlelemen and potman.

GROUP 6: Powderman, master form setters.

GROUP 7: Brick paver (asphalt block paver, asphalt block sawman, asphalt block grinder, hastings block or similar type)

GROUP 8: Licensed powdermen.

-----  
LABO0657-004 06/01/2006

	Rates	Fringes
Laborers: (HAZARDOUS WASTE REMOVAL, EXCEPT ON MECHANICAL SYSTEMS: Preparation for, removing and encapsulation of hazardous materials from non-mechanical systems)		
Skilled Asbestos Abatement Laborers.....	\$ 15.99	3.84
Skilled Toxic and		

Hazardous Waste Removal  
 Laborers.....\$ 18.61 3.84

-----  
 LABO0657-005 06/01/2006

	Rates	Fringes
Laborers: (TUNNEL, RAISE & SHAFT (FREE AIR) FOR HEAVY AND SEWER & WATER LINES CONSTRUCTION)		
GROUP 1.....	\$ 19.82	3.84
GROUP 2.....	\$ 20.39	3.84
GROUP 3.....	\$ 21.85	3.84
GROUP 4.....	\$ 22.47	3.84

LABORERS CLASSIFICATIONS:

GROUP 1: Brakeman, Bull Gang, Dumper, Trackmen, Concrete Man.

GROUP 2: Chuck Tender, Powdermen in Prime House, Form Setters and Movers, Nippers, Cableman, Houseman, Groutman, Bell or Signalman, Top or Bottom Vibrator Operator.

GROUP 3: Miners, Re-Bar Underground, Concrete or Gunnite Nozzlemen, Powdermen, Timbermen and Re-Timbermen, Wood Steel Including Liner plate or Other Support, Material Motorman, Caulkers, Diamond Drill Operators, Riggers, Cement Finishers-Underground, Welders and Burners, Shield Driver, Air Trac Operator, Shotcrete Nozzlemen and Potman.

GROUP 4: Mucking Machine Operator (Air).

-----  
 LABO0657-006 06/01/2006

	Rates	Fringes
Laborers: (TUNNEL, RAISE AND SHAFT (COMPRESSED AIR) FOR HEAVY CONSTRUCTION ONLY		
Gauge Pressure Work Period		
(Pounds)	(Hours)	
1-14	7.....	\$ 24.16 3.84
14-18	6.....	\$ 28.43 3.84

FOOTNOTE: On any requirement for air pressure in excess of 18 PSI, work periods and rates should be negotiated at a pre-bid conference.

-----  
 LABO0657-007 06/01/2006

	Rates	Fringes
Laborers: (PAVING AND INCIDENTAL GRADING)		
Asphalt Raker & Concrete Saw Operator.....	\$ 16.76	4.10

Asphalt Shoveler.....	\$ 16.23	4.10
Asphalt Tammer & Concrete Shoveler.....	\$ 16.47	4.10
Jack Hammer.....	\$ 16.66	4.10
Laborer.....	\$ 16.12	4.10
Sand Setter & Form Setter...	\$ 17.37	4.10

-----  
 \* MARB0002-003 05/01/2007

	Rates	Fringes
Marble & Stone Mason Includes Pointing, Caulking and Cleaning of All Types of Masonry, Brick, Stone and Cement Structures.....	\$ 31.00	11.52

-----  
 \* MARB0003-001 05/01/2007

	Rates	Fringes
Mosaic & Terrazzo Worker, Tile Layer Marble Mason and Tile Layer.	\$ 24.67	8.78
Terrazzo Worker.....	\$ 25.42	8.78

-----  
 \* MARB0003-004 05/01/2007

	Rates	Fringes
Marble, Tile & Terrazzo Finisher.....	\$ 19.84	7.90

-----  
 PAIN0051-001 06/01/2006

	Rates	Fringes
Painters: All Industrial Work.....	\$ 23.48	7.31
Bridges, Heavy Highway, Lead Abatement and Flame/Thermal Spray.....	\$ 26.37	7.31
Commercial and Mold Remediation, Painters, Wallcovers and Drywall Finishers.....	\$ 22.06	7.31
Metal Polishing and Refinishing.....	\$ 23.06	7.31

-----  
 PLAS0891-001 05/01/2007

	Rates	Fringes
Cement Masons: HEAVY CONSTRUCTION ONLY.....	\$ 26.15	6.01

-----

PLAS0891-002 06/01/2007

	Rates	Fringes
Cement Masons: (PAVING & INCIDENTAL GRADING)		
Cement Masons.....	\$ 17.35	4.35
Concrete Saw Operators.....	\$ 17.35	4.35
Form Setters.....	\$ 17.35	4.35

-----  
PLUM0005-001 08/01/2006

	Rates	Fringes
Plumber.....	\$ 31.52	12.59+a

a. PAID HOLIDAYS: Labor Day, Veterans' Day, Thanksgiving Day and the day after Thanksgiving, Christmas Day, New Year's Day, Martin Luther King's Birthday, Memorial Day and the Fourth of July.

-----  
PLUM0602-005 08/01/2006

	Rates	Fringes
Steamfitter, Refrigeration & Air Conditioning Mechanic.....	\$ 31.27	12.82+a

a. PAID HOLIDAYS: New Year's Day, Martin Luther King's Birthday, Memorial Day, Independence Day, Labor Day, Veterans Day, Thanksgiving Day and the day after Thanksgiving and Christmas Day.

-----  
SHEE0100-001 07/01/2006

	Rates	Fringes
Sheet Metal Worker.....	\$ 30.39	11.05

-----  
TEAM0639-001 03/07/2004

	Rates	Fringes
Truck drivers: (HEAVY & HIGHWAY CONSTRUCTION)		
Tandem & Triaxle (3 or more axles, including steering axle).....	\$ 16.00	5.82+a
Tractor-trailer, Low Boy....	\$ 20.00	5.82+a

a. VACATION: Employees will receive one (1) week's paid vacation after one (1) year of service.

-----  
TEAM0639-002 06/01/2005

	Rates	Fringes
--	-------	---------



for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations  
Wage and Hour Division  
U.S. Department of Labor  
200 Constitution Avenue, N.W.  
Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator  
U.S. Department of Labor  
200 Constitution Avenue, N.W.  
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board  
U.S. Department of Labor  
200 Constitution Avenue, N.W.  
Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

=====

END OF GENERAL DECISION

CABLE SUMMARY							
FROM STATION	TO STATION	DISTANCE	4/0	#8	#10	#8 GRND	#2 GRND
949925	M7	11	63				21
M7	L8	18			54	28	
M7	M10	70	240				80
M7	M8	74	252				84
M7	L7	100	330				110
M10	L11	15			75	25	
M10	M9	91	303				101
M9	L10	14			72	24	
M8	L9	14			72	24	
L7	M6	66	228				76
M6	JB3	25	105				35
JB3	JB2	19	87				29
JB2	JB1	106	348				116
JB1	M2	20	90				30
M2	M3	44	162				54
M3	JB5	59	207				69
JB 5	JB6	77	261				87
JB 5	JB4	184	582				194
JB 4	'O'	7		51			17
'O'	EX. HB	103		339			113
JB 2	L6	3			39	13	
JB 6	L5	3			39	13	
M2	L4	34			132	44	
M2	L1	301		933		311	
JB 4	L3	3			39	13	
EX. HB	L2	3			39	13	
CABLE QUANTITIES			3258	1323	561	508	1216