

REQUEST FOR QUOTATION <i>(THIS IS NOT AN ORDER)</i>		Install Barrier Fence and Net for Watkins Field, Wash. DC		PAGE OF PAGES (incl. Cover) 1 4 (+ Attachment-A & B)	
1. REQUEST NO. RFQ-DCHA-2009-Q-0031	2. DATE ISSUED 04-29-08	3. REQUISITION NO. RQ567720	4. COMMODITY GROUP AND CLASS OCP/DPR →	CODE	
5A. ISSUED BY Office Of Contracting And Procurement 441 4 th Street, NW. 700 South Washington, DC 20001			6. DELIVER BY (Date) / All work shall be satisfactorily completed: 60 days after NTP or July 31, 2009, whichever is earlier.		
5B. FOR INFORMATION CALL: (Name and telephone no.) (No collect calls) Ray Sharma , Sr. Contract Specialist (Voice) 202-724-5240 Fax: 202-727-8850, email: ramesh.sharma@dc.gov			7. DELIVERY <input checked="" type="checkbox"/> FOB DESTINATION <input type="checkbox"/> OTHER (See Schedule)		
8. TO: NAME AND ADDRESS, INCLUDING Zip Set aside for "DC Certified CBE/SBE/LSDBE contractors only"			9. DESTINATION (Consignee and address, including ZIP code) Sherry Frear, Project Manager Dept. of Parks & Recreations (DPR) 3149- 16 th St. NW, Wash. DC 20010 (Ph: 202-671-0365)		
10. PLEASE DELIVER QUOTATIONS TO THE ISSUING OFFICE (see box-5a) WITH FOLLOWING NOTATION ON OUTSIDE COVER : " ATTN: RAY SHARMA – OCP) and must be received in the Bid Room (see address in Box-5A) on or before: May 6, 2009 (2.00 pm EST)		11. BUSINESS CLASSIFICATION (Check appropriate boxes) CBE/SBE/LSDBE Cert. No.:, Expires on: Total Pref. Points: <input type="checkbox"/> SMALL <input type="checkbox"/> RESIDENT-OWNED <input type="checkbox"/> DISADVANTAGED <input type="checkbox"/> WOMEN-OWNED <input type="checkbox"/> ENTERPRISE ZONE			
IMPORTANT: This is a request for information, and quotations furnished are not offers. If you are unable to quote, please so indicate on this form and return it. This request does not commit the Government to pay any costs incurred in the preparation of the submission of this quotation or to contracts for supplies or invoices. Supplies are of domestic origin unless otherwise indicated by quoter. Any representations and/or certifications attached to this Request for Quotations must be completed by the quoter.					
12. SCHEDULE (Include applicable Federal, State and local taxes)					
ITEM NO. (a)	SUPPLIES/SERVICES (b)	QUANTITY (c)	UNIT (d)	UNIT PRICE (e)	Total AMOUNT (f)
001	Lump sum price for all labor, material, equipment, supplies and other incidentals for completion of all the work and related services for removal an disposal of the existing fence, and installation of the new fence and net as described in the <u>attached Statement Of Work (SOW), Conceptual Plan and Aerial Site Image.</u> <u>NOTE:</u> 1. This RFQ is subject to the latest Davis Bacon Wage Determination Rates for Building Construction Trades which can be freely downloaded from: www.usdol.gov .	1	Lump sum	n/a
13. DISCOUNT FOR PROMPT PAYMENT		10 CALENDAR DAYS %	20 CALENDAR DAYS %	30 CALENDAR DAYS %	CALENDAR DAYS %
14. NAME AND ADDRESS OF QUOTER (Street, city, county, State and ZIP Code)			15. SIGNATURE OF PERSON AUTHORIZED TO SIGN THE QUOTATION		16. DATE OF QUOTATION
			17. NAME AND TITLE OF SIGNER ABOVE (print)		18. TELEPHONE NO. (Include area code)

GOVERNMENT OF THE DISTRICT OF COLUMBIA
Department of Parks and Recreation

**Statement of Work
for
Barrier Fence and Net
at
Watkins Field
420 12th Street, SW, Washington, D.C.**

April 28, 2009

1. PROJECT SUMMARY

The District of Columbia Department of Parks & Recreation ("DPR") seeks the services of a contractor to install a barrier fence and net at Watkins Field (the "project").

The intent of the project is to prevent foul balls from striking vehicles and pedestrians.

2. SITE DESCRIPTION

2.1. Location

Watkins Field (the "site") is adjacent to Watkins Recreation Center at 420 12th Street, SE. The site is bounded at the south by E Street, SE.

2.2. Background

The existing chain link fence along E Street is insufficient for stopping high-flying balls and the community has requested a more effective barrier.

3. DESCRIPTION OF WORK

3.1. Generally

Contractor shall provide all labor, materials, equipment and supplies to

- a) remove and dispose of existing chain link fence, top rails, cross-braces/stiffeners, and gates;
- b) patch holes in wall as a result of removal of existing posts, and install skateboard deterrents;
- c) design, fabricate and install new chain link fence with all supporting components approximately 10.5' north of existing wall;
- d) design, fabricate and install approximately 280 linear feet of barrier net as described at Section 3.3 "Specifications," below;
- e) install new landscaping in open area between new chain link fence and wall.

3.2. Key Dates

DPR seeks to have the project completed by July 31, 2009, or required completion date under Section-4 below (period of Performance) whichever is earlier.

3.3. Specifications

3.3.1. Fence and Net

Contractor shall ensure that the fence meets the following minimum specifications.

- A. Barrier net shall be 24' tall, as measured from top of existing chain link fence.
- B. Barrier net shall be installed at top rail of chain link fence.
- C. Nylon netting, Cascades Nets (Bellingham, Washington), or equal
 - 1) high tenacity twisted knotted 1-3/4" nylon netting
 - 2) diamond mesh netting construction
 - 3) UV and water resistant
 - 4) 3/8" black polyester rope (4000 lb breaking strength) sewn to perimeter of each net
- D. Net support: steel tube, min. 14 gauge, 6" O.D., with min. 5' concrete footing.
- E. Net support, top and bottom: vinyl-coated, galvanized cable
- F. Hardware: All nuts, bolts, cleats, eyebolts, turnbuckles, swivels, snap hooks, etc. required for a complete installation.

3.3.2. Landscaping

The area between existing wall and new chain link/barrier net shall be landscaped as follows:

- A. Low-growing (max. 8") evergreen shrub. Genus and species to be approved by COTR.

3.3.3. Existing Wall Repair

- A. Cut all posts level with top-of-wall and sand smooth.
- B. Backfill all holes with concrete.
- C. Install skateboard deterrents, e.g., SKATESTOPPERS® Architectural Series (AS) Skateboard Deterrent, or equal. Style to be approved by COTR prior to ordering.
 - 1. Install approximately every 36" +/- 6"; layout to be dictated by uniformity of spacing relative to joints.

3.4. Protection of Existing Elements

Contractor shall protect all existing elements, including but not limited to public utilities, trees, playing fields, furnishings, play equipment and pavement.

3.5. Demolition

Contractor shall remove and dispose off site of existing barrier net, fence posts, concrete and any and all other debris associated with removal of the existing barrier net.

3.6. Execution

- A. Contractor shall be responsible for field verifying all measurements and dimensions.
- B. Contractor shall provide laborers and supervisors who are thoroughly familiar with the type of construction involved and materials and techniques specified.
- C. Contractor shall ensure that there is a supervisor on site at all times the work is being performed.
- D. Contractor shall coordinate all work with Contracting Officer's Technical Representative ("COTR") to ensure no conflict with use of field by athletic groups.

3.7. Cleaning

- A. Contractor shall clean the jobsite of excess materials DAILY.
- B. Upon completion of installation, Contractor shall ensure all items installed pursuant to this Statement of Work are cleaned of all dirt and debris.

3.8. Site Restoration

Contractor shall reseed all areas disturbed by the work, except that Contractor shall re-sod any area in excess of twenty (20) square feet disturbed by the work.

4. PERIOD OF PERFORMANCE

Contractor shall have a maximum of sixty (60) calendar days after issuance of written Notice To Proceed signed by the Contracting Officer.

5. FORMATS AND CONVENTIONS

Contractor shall provide all cost information according to the divisions and sections using The Construction Specifications Institute "Master Format" format numbering system.

6. CONTRACTING OFFICER:

The Contracting Officer for this contract is:

Diane Wooden
Office of Contracting and Procurement (OCP)
441-4th St. NW, Suite # 700-S
Washington, DC 20001
PH: 202724-2163

7. CONTRACTING OFFICER TECHNICAL REPRESENTATIVE

The Contracting Officer Technical Representative for this contract is:

Sherry A. Frear, ASLA
Landscape Architect
Department of Parks and Recreation (DPR)
Office of Planning & Capital Projects
3149 16th Street, NW
Washington, DC 20010
202-671-0365
sherry.frear@dc.gov

8. ATTACHMENTS

- A Aerial image of site.
- B Conceptual Plan of proposed barrier fence and net.